
15-191-00119-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Sumner County. Sec. 33 Twp. 30S Rge. (E) 1 (W)

Location as "NE/CNW¼SW¼" or footage from lines NE NW SE

Lease Owner Thunderbird Drilling, Inc.

Lease Name Proud Well No. 1

Office Address 712 Union Center, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed October 9 19 60

Application for plugging filed October 9 19 60

Application for plugging approved October 9 19 60

Plugging commenced October 9 19 60

Plugging completed October 9 19 60

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel

Producing formation Depth to top Bottom Total Depth of Well 3980 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS — CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole to 300' with heavy mud. Plug 1-1/4th sacks of hulls - 15 sacks cement mixed and poured through drill pipe. Filled hole to 35'. Plug - 10 sacks cement, 1-1/4th sacks hulls - 2 sacks in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Thunderbird Drilling, Inc.

Address 712 Union Center, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick ss.

Charles W. Aikins, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Aikins, Jr.

Charles W. Aikins, Jr., President
712 Union Center, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of October, 19 60

Rose Marie Kuhlman
Notary Public.

My commission expires February 1, 1964

5-44M

15-191-00119-0000

DRILLERS LOG

#1 PROUD

LOCATION: NE NW SE - Section 33
Township 30S, Range 1W
Sumner County, Kansas

CONTRACTOR: Thunderbird Drilling, Inc.
712 Union Center
Wichita 2, Kansas

SURFACE CASING: 8-5/8" surface casing set at 436' with 250 sacks cement, 3% gel, 4 sacks calcium chloride.

ELEVATION: 1257' K. B.
1254' D. F.
1252' G. L.

DRILLING COMMENCED: September 24, 1960

DRILLING COMPLETED: October 9, 1960

WELL LOG

0 - 70	Clay, Sand and Shale
70 - 300	Shale and Shells
300 - 398	Broken Lime
398 - 436	Lime and Shale
436 - 455	Shale and Lime
455 - 970	Lime and Shale
970 - 2255	Shale and Lime
2255 - 2514	Lime and Shale
2514 - 2633	Shale and Lime
2633 - 2644	Sand
2644 - 2730	Sand and Shale
2730 - 2940	Shale and Lime
2940 - 3200	Lime
3200 - 3305	Lime and Shale
3305 - 3365	Lime
3365 - 3587	Lime and Shale
3587 - 3617	Cherty Lime and Shale
3617 - 3684	Lime and Shale
3684 - 3714	Cherty Lime and Shale
3714 - 3907	Lime and Shale
3907 - 3912	Lime
3912 - 3956	Shale
3956 - 3969	Shale and Lime
3969 - 3980	Sand
3980	Total Depth

RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1960
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, Charles W. Aikins, Jr., an officer of Thunderbird Drilling, Inc., hereby certifies that the above is a true and correct log of the formations encountered in the drilling of the #1 Proud as shown in the daily drilling reports.

THUNDERBIRD DRILLING, INC.

Charles W. Aikins, Jr., President

Subscribed and sworn to before me this 13th day of October, 1960.

Rose Marie Kuhlman, Notary Public

My commission expires 2-1-64.