

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Sumner County, Sec. 30 Twp. 30S Rge. (E) 1 (W)

Location as "NE/CNW/SW" or footage from lines SE SW  
Lease Owner Beardmore Drilling Company  
Lease Name Edwards "A" Well No. 1  
Office Address 700 - 120 Bldg., Wichita, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 3-18 19 67  
Application for plugging filed 3-18 19 67  
Application for plugging approved 3-18 19 67  
Plugging commenced 3-18 19 67  
Plugging completed 3-18 19 67  
Reason for abandonment of well or producing formation dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well Paul Turpin  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4164 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Shale		0	240'			
Shale and Shells		240'	432'	8-5/8"	432'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

0 to	35'	-	10 sacks cement
	35'	-	wood plug
35' to	160'	-	heavy mud
160' to	220'	-	20 sacks cement
	220'	-	wood plug
220' to	4164'	-	heavy mud

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 30 1967  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Shawver-Armour, Inc.  
Address 817 Central Bldg., Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Heber Beardmore (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
700 - 120 Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 21st day of March, 19 67  
Leonard P. Tolle  
Leonard P. Tolle Notary Public.

My commission expires 1-28-68

D R I L L E R ' S L O G

FARM NAME: EDWARDS A #1 LOCATION: SE SW 30-30S-1W  
 Sumner County, Kansas  
 CONTRACTOR: SHAWVER-ARMOUR, INC.  
 OWNER: BEARDMORE DRILLING CO. ELEVATION: 1314' KB  
 COMMENCED: March 1, 1967 COMPLETED: March 18, 1967  
 CASING RECORD: 433' 8-5/8" w/300 sacks HA 5 Cement - 1" w/40 sacks  
 Hole D & A

FORMATION:

TOPS:

Top Soil & Shale 240  
 Shale & Shells 395  
 Anhydrite 433  
 Lime & Shale 2771  
 Sand 2812  
 Lime & Shale 3090  
 Kansas City Lime 3125  
 Lime 3474  
 Lime & Shale 3584  
 Shale & Lime 3640  
 Shale 3710  
 Lime & Shale 3739  
 Mississippi Chert 3748  
 Core #1 3750-3760  
 Core #2 3760-3770  
 Mississippi 3798  
 Lime & Shale 3853  
 Lime 3875  
 Shale & Lime 3915  
 Lime 3971  
 Lime & Shale 3996  
 Lime 4040  
 Lime & Shale 4094  
 Lime 4115  
 Kinderhook Shale 4115  
 Shale 4146  
 Sand 4154  
 Simpson Sand 4164  
 Rotary Total Depth 4164  
 D & A

T Kansas City 3086  
 B Kansas City 3334  
 Cherokee 3579  
 Mississippi Chert 3739  
 Mississippi Lime 3749  
 Kinderhook Shale 4115  
 Simpson Sand 4147

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAR 30 1967  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS }  
 SEDGWICK COUNTY } SS

I, JAMES M. ARMOUR, do hereby certify that the above log is a true and correct copy of the above captioned well as shown on the daily drilling reports.

SHAWVER-ARMOUR, INC.

By James M. Armour  
 James M. Armour

Subscribed and sworn to before me this 21st day of March, 1967.

My commission expires Dec. 29, 1967

Marjorie Hall  
 Marjorie Hall, Notary Public