

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Sumner County, Sec. 30 Twp. 30 Rge. 1 (X) (W)

Location as "NE/CNW/SW" or footage from lines NE NE NE

Lease Owner Shawver-Armour, Inc.

Lease Name Luther Well No. 1

Office Address 817 Central Building

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 1- 27 19 58

Application for plugging filed 1- 27 19 58

Application for plugging approved 1- 27 19 58


Plugging commenced 1- 27 19 58

Plugging completed 1- 27 19 58

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gene Graham

Producing formation Simpson Depth to top 3969 Bottom 3991 Total Depth of Well 3991 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	Water	0	388'	8 5/8"	388'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed; from _____ feet to _____ feet for each plug set.

Circulated heavy mud, lay down pipe then heavy mud to 240'
1 Plug @ 240' Halliburton Plug and 1/2 sk. hulls
15 sks cement put in dry if fluid
is @ 240' if not put in thru drill pipe
then heavy mud to 35'
2 Plug @ 35' Halliburton Plug and 1/2 sk Hulls
10 sks to base of cellar

RECEIVED
STATE CORPORATION COMMISSION

FEB 7 1958

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Shawver-Armour, Inc.
Address 817 Central Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
JAMES ARMOUR (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Armour
JAMES ARMOUR
817 Central Building, Wichita, Kans.
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of January, 19 58

My commission expires Dec. 29th, 1959

Marjorie Hall
MARJORIE HALL
Notary Public.

PLUGGING
FILE SEC 30 T. 30 R. 14
BOOK PAGE 79 LINE 29

DRILLERS REPORT

COMPANY: SHAWVER-ARMOUR, INC.
CONTRACTOR: SHAWVER-ARMOUR, INC.
COMMENCED: January 14, 1958

LOCATION: NE NE NE Sec. 30-30-1W
Sumner County, Kansas
ELEVATION: 1289 D. F.
COMPLETED: January 27, 1958

Farm Name: Luther 1

CASING RECORD

388' 8 5/8ths" W/325 Sx. 2% cc Blended

FORMATION

TOPS

Shale & Chalky Lime	320
Anhydrite	388
Anhydrite Lime & Shale	510
Lime & Shale	1365
Shale & Lime	1680
Lime & Shale	2240
Shale & Lime	2440
Lime & Shale	2580
Shale & Lime	2705
Stalnaker Sand & Shale	2815
Lime & Shale	2815
Lime & Shale	2925
Shale	3005
Kansas City Lime	3168
Lime & Shale	3389
Shale & Lime	3434
Lime & Shale	3590
Shale & Lime	3652
Mississippi Lime	3740
Mississippi Lime & Shale	3812
Mississippi Lime & Chert	3816
Lime	3870
Lime & Chert	3903
Lime	3940
Kinderhook	3969
Simpson	3977
Simpson Sand & Shale	3991 RTD.

Stalnaker	2705
Kansas City	3005
Mississippian	3648
Kinderhook	3940
Simpson	3969

STATE OF KANSAS)
)ss
SEDGWICK COUNTY)

I, James Armour, do hereby certify that the above is a true and correct copy of the log on the above captioned well, as shown on the daily drilling reports.

SHAWVER-ARMOUR, INC.

BY James Armour
JAMES ARMOUR

Subscribed and sworn to before me this
27th day of January, 1958

My Commission expires December 29th, 1959

Marjorie Hall
MARJORIE HALL NOTARY PUBLIC

RECEIVED
STATE CORPORATION COMMISSION

FEB 7 1958

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 30 T 30 R 4
BOOK PAGE 79 LINE 29