

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Summer County. Sec. 28 Twp. 30 Rge. 1W (E) (W)

Location as "NE/CNW/SW" or footage from lines. NE NE NE

Lease Owner Capitt Drilling, Inc.

Lease Name Hinshaw Well No. 1

Office Address 1005 Central Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 1 1955

Application for plugging filed December 1 1955

Application for plugging approved December 1 1955

Plugging commenced December 1 1955

Plugging completed December 1 1955

Reason for abandonment of well or producing formation oil in commercial quantities not found.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. G. Buffington

Producing formation Depth to top Bottom Total Depth of Well 3987 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	286'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with extra heavy rotary mud from 3987' to 286'. Set plug #1 with 15 sacks cement. Filled hole with extra heavy rotary mud from 245' to 30'. Set #2 plug with 10 sacks cement. Welded steel plate on surface pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Capitt Drilling, Inc.

Address 1005 Central Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF Sedgwick, ss.

L. J. Clampitt (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature] 1005 Central Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 7th day of December, 1955

My commission expires September 30, 1959

[Notary Seal] Notary Public.

PLUGGING
PAGE 28 T. 30 R. 1W
BOOK PAGE 21 LINE 24

DEC 8 - 1955
CONSERVATION DIVISION
Wichita, Kansas

ROTARY DRILLING LOG

OPERATOR: Capitt Drilling, Inc.
Hinshaw #1
NE NE NE Sec. 28-30-1W,
Sumner County, Kansas

CONTRACTOR: Capitt Drilling, Inc.
COMM: 11/14/55
COMP: 12/1/55

Formations:

Shale & Shells	286'
Shale & Lime	1315'
Sandy Shale & Shells	1500'
Shale & Lime	2613'
Sand (Layton)	2720'
Shale & Lime	2693'
Sandy Shale	2719'
Shale & Lime	2926'
Lime (Kansas City)	3160'
Shale & Lime Streaks	3215'
Shale & Shells	3298'
Shale & Lime	3399'
Lime & Shale (Breaks)	3440'
Shale & Lime	3517'
Lime	3550'
Lime & Chert	3555'
Lime	3842'
Shale	3851'
Shale & Lime (Streaks)	3882'
Shale	3891'
Shale & Lime	3957'
Sand	3987'
Rotary Total Depth (D & A)	3987'

Remarks: Set 8-5/8" surface casing at 286' cemented with 300 sacks regular cement and 3 sacks C.C.

We certify the above log is true and correct to the best of our knowledge and belief.

CAPITT DRILLING, INC.

R.R. McNicol

R. R. McNicol

PLUGGING
WELL NO. 28-30-1W
BOOK PAGE 21 LINE 24

RECEIVED
STATE CORPORATION COMMISSION
DEC 8 - 1955
CONSERVATION DIVISION
Wichita, Kansas