


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

SUMNER County. Sec. 27 Twp. 30S Rge. ~~(E)~~ 1 (W)

Location as "NE/CNW/SW" or footage from lines NW NW SW
Lease Owner MONARCH OIL & GAS COMPANY
Lease Name STEWART TRUST Well No. 1
Office Address 1005 WICHITA PLAZA, WICHITA, KANSAS 67202
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed JULY 11, 1966
Application for plugging filed JULY 13, 1966
Application for plugging approved (BY PHONE) JULY 11, 1966
Plugging commenced JULY 11, 1966
Plugging completed JULY 11, 1966
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well HOWARD HESS
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3964 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	365'	8-5/8"	365'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

FILLED HOLE WITH HEAVY MUD TO 250 FEET. SET FIRST PLUG @ 250 FT. W/ 1/2 SACK HULLS AND 20 SACKS CEMENT. FILLED HOLE WITH HEAVY MUD TO 35 FEET. SET SECOND PLUG @ 35 FT. W/ 1/2 SACK HULLS AND 8 SACKS CEMENT. PLUGGED RAT HOLE W/ 2 SACKS CEMENT. JOB COMPLETED @ 4:30 AM, JULY 11, 1966.

RECEIVED
STATE CORPORATION COMMISSION

JUL 15 1966

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GABBERT-JONES, INC.
Address 514 ORPHEUM BLDG., WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
JAMES S. SUTTON (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *James S. Sutton*
514 ORPHEUM BLDG., WICHITA, KANSAS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 13TH day of JULY, 1966

Barbara J. Layton
BARBARA J. LAYTON Notary Public.

My commission expires FEBRUARY 1, 1968

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

STEWART TRUST #1
NW NW SW SECTION 27-30S-1W
SUMNER COUNTY, KANSAS

COMMENCED: JUNE 30, 1966
COMPLETED: JULY 11, 1966

OPERATOR - MONARCH OIL & GAS COMPANY

DEPTH		FORMATION	REMARKS
FROM	TO		
0	438	SHALE AND LIME	RAN 9 JOINTS 8-5/8" CASING, SET @ 365' w/300 SX. CEMENT.
438	650	LIME	
650	1225	LIME AND SHALE	
1225	1940	SHALE AND SHELLS	
1940	2115	LIME AND SHALE	
2115	2215	SHALE AND LIME	
2215	2315	LIME	
2315	2497	SHALE AND LIME	
2497	2710	SHALE AND SAND	
2710	2915	LIME AND SHALE	
2915	3131	LIME	
3131	3381	LIME AND SHALE	
3381	3470	SHALE AND LIME	
3470	3570	LIME AND SHALE	
3570	3915	LIME	
3915	3964	SHALE	
3964	TD		DRY AND ABANDONED.

RECEIVED
STATE CORPORATION COMMISSION
JUL 15 1966
CONSERVATION DIVISION
Wichita, Kansas

I, JAMES S. SUTTON, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE NW NW SW SECTION 27-30S-1W, SUMNER COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

James S. Sutton

JAMES S. SUTTON

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 13TH DAY OF JULY, 1966, PERSONALLY APPEARED JAMES S. SUTTON, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton

BARBARA J. LAYTON, NOTARY PUBLIC

MY COMMISSION EXPIRES FEBRUARY 1, 1968.