

1 051738
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

11-4 15-033-10029-0001

API NUMBER 15- Docket #D-13,120 cancelled in 1986
C NW NE, SEC. 24, T 32 S, R 20 W XX
4620 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 30208
Operator: Tri-J Tubulars, Inc.
Name & Address: 125 N. Market, Ste. 1532
Wichita, KS 67202

Lease Name Martin D. Well / 1
County Comanche
Well Total Depth 5300 172.25 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 547

Abandoned Oil Well Gas Well Input Well SWD Well X O&A
Other well as hereinafter indicated

Plugging Contractor DS&W Well Servicing, Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 11 a.m. Day: 4 Month: 11 Year: 19 93

Plugging proposal received from Joe Strube
(company name) DS&W Well Servicing, Inc. (phone) 316-587-3361

well: 4 1/2" at 5264' w/100 sx cement, PBD 5223', Perfs at 5140-84'
1st plug sand back to 5090' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper
plug and pump 150.sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None
Operations Completed: Hour: 12:45 p.m. Day: 4 Month: 11 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded back to 5090' and dumped 4 sx cement on top of
sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls. released
8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2524' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED
DATE NOV 23 1993
INV. NO. 39307

Signed Richard W. Lucas (TECHNICIAN)

RECEIVED
STATE CORPORATION COM
NOV 08 1993

CONSERVATION DIVISION
Wichita, Kansas