

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-00236-00-00
Spot: C Sec/Twnshp/Rge: 15-32S-40W
2620 feet from N Section Line, 2620 feet from E Section Line
Lease/Unit Name: EVANS B Well Number: 1
County: MORTON Total Vertical Depth: 2383 feet

Operator License No.: 5952 Conductor Pipe: Size _____ feet: 877.45
Op Name: BP AMERICA PRODUCTION COMPANY Surface Casing: Size 10.75 feet: 545 WITH 350 SX CMT
Address: 2225 WEST OKLAHOMA AVENUE Production: Size 7 feet: 2232 WITH 350 SX CMT
ULYSSES, KS 67880 Liner: Size _____ feet: _____

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/07/2002 1:00 PM
Plug Co. License No.: 5287 Plug Co. Name: HALLIBURTON SERVICES
Proposal Rcvd. from: CAREY SPOHN Company: BP AMERICA Phone: (620) 356-6955

Proposed Plugging Method: CIBP @ 1200'. RUN COIL TUBING TO 1200' & SPOT 225 SX CMT. PRFORATE AT 600'. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 11/07/2002 7:15 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:
OPEN HOLE. CIBP @ 1200. RAN COILED TUBING TO 1200'. PUMP 125 SX 65/35 POZMIX 6% GEL & FILLED 7" CASING TO 600'. PERFORATED AT 600' & TIED ON 7" & PUMPED 200 SX 60/40 POZMIX 6% GEL. CIRCULATED CMT TO SURFACE (18 BBLs TO PIT). BOTH SIDES FULL OF CMT.

RECEIVED
NOV 20 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY HALLIBURTON. NO CASING RECOVERED.

Plugged through: TBG

District: 01

RECEIVED
NOV 12 2002
KCC Dodge City

Signed Jim Holland (TECHNICIAN)
INVOICED
DATE 11-21-02
INV. NO. 2003060848