

1 020136

4-16-88 15-189-00031-0001 156 R  
API NUMBER 15- Docket #D-15,352

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION 70' E C SW/4, SEC. 15, T 34 S, R 38 W/EX  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

1320 feet from S section line  
3890 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 6568

Lease Name Kelley B Well # 1-A  
County Stevens 214.18

Operator: Kaiser-Francis Oil Company  
Name & Address P.O. Box 21468  
Tulsa, OK 74121-1468

Well Total Depth 6590 feet  
Conductor Pipe: Size 13 3/8 feet 599  
Surface Casing: Size 8 5/8 feet 1769

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well  D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kaiser-Francis Oil Company License Number 6568  
Address P.O. Box 21468, Tulsa, OK 74121-1468

Company to plug at: Hour: 6 p.m. Day: 15 Month: 4 Year: 19 88

Plugging proposal received from Randy Bell  
(company name) Kaiser-Francis Oil Company (phone) 918-494-0000

were: PBDT 1780' Open hole 1712' 4 1/2" shot off at 2210' when completed for SWD and recovered.  
Plug pumped there TOC.

1st plug at 1712' with 50 sx cement,  
2nd plug at 600' with 50 sx cement,  
3rd plug at 40-0' with 10 sx cement.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:45 a.m. Day: 16 Month: 4 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 100 sx cement at 1740' on 4/15/88, tagged TOC  
at 1759' on 4/16/88 with 2 7/8" tubing.

RECEIVED  
STATE CORPORATION COMMISSION

2nd plug pumped 50 sx cement at 620',  
3rd plug pumped 200 sx down 13 3/8",

APR 22 1988

4th plug pulled tubing to 40' and pumped 10 sx to surface.  
8 5/8" & 13 3/8" full on 4/15/88.

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used Class C cement by Western Cement Company. No casing recovery.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
Observe this plugging.

Signed Glen R. Barlow  
(TECHNICIAN)

DATE 4-27-88

INV. NO. 20483