


To: 1 100104 3-10
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

15-127-06257-0000
API NUMBER 15- Completion date 6/13/57

TECHNICIAN'S PLUGGING REPORT
Operator License / 4549
Operator: Anadarko Petroleum Corporation
Name:
Address P.O. Box 351
Liberal, KS 67905-0351



NE NE NE SW, SEC. 34, T 32 S, R 40
2480 feet from S section line
2840 feet from E section line
Lease Name Blucher Well # 1-34
County Morton 77.90
Well Total Depth 2397 feet
Conductor Pipe: Size feet
Surface Casing: Size 10 3/4 feet 416

Abandoned Oil Well Gas Well X Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 12 p.m. Day: 10 Month: 3 Year: 19 97

Plugging proposal received from Don Horton
(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

Work: 7" at 2244', 5 1/2" liner from 2224-2397', Perfs at 2244-2397'
1st plug set CIBP at 2100',
2nd plug perforate at 466-467' and pump 100 sx cement,
3rd plug top off from 40-0'.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None
Operations Completed: Hour: 5 p.m. Day: 10 Month: 3 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2100' with 2' sx cement on top,
Perforated at 466-467' and circulated with 9# mud,
2nd plug spotted 100 sx cement at 50' above the perfs, Circ. annulus to surface
3rd plug topped off from 40-0' with 15 sx cement.

KANSAS RECEIVED
CORPORATION
MAY 18 12:02 PM '97

Remarks: Used common cement by Sargent & Horton. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED
This (company) observe this plugging.

Signed Gary W. Miller
(TECHNICIAN)

DATE ~~MAR 18 1997~~

INV. NO. 47763

3-10 MAY 21 1997