

To: 1 020445
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-23

API NUMBER 15-129-20,654-0000 204
C N/2 SE, SEC. 4, T. 32 S, R. 41 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5992

Operator: Patton Oil Company
Name & Address: 5660 S. Syracuse Circle, Ste. 200
Englewood, CO 80111

Lease Name Claridge Well # 1

County Morton

Well Total Depth 5290 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 735

Abandoned Oil Well _____ Gas Well _____ X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 3 p.m. Day: 20 Month: 3 Year: 19 92

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 5275' w/150 sx cement, PBTD 5253', Perfs at 5188-5205'

1st plug pump 1 sx hulls and 20 sx cement at perfs, displace with mud,

2nd plug load hole with mud and pump 50 sx cement at 1600',

3rd plug pump 50 sx cement at 750',

4th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 6 p.m. Day: 23 Month: 3 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement at perfs, displaced with mud,

2nd plug loaded hole with mud, pumped 50 sx cement at 1600',

3rd plug pumped 50 sx cement at 750',

4th plug pumped 10 sx cement at 40 to -4'.

Remarks: Used common cement by Sargent's. Recovered 2510' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

observe this plugging.

DATE 4-22-92

INV. NO. 34987

3-23 JUL 08 1992

Signed Glenn R. Barlow (TECHNICIAN)

STATE CORPORATION COMMISSION
RECEIVED
MAR 27 1992
CONSERVATION DIVISION
Wichita, Kansas