

1 031357

To: STATE CORPORATION COMMISSION OCT 01 1995
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-129-21,401-0000
SE NE SW, SEC. 10, T 32 S, R 41 W/E
1390 feet from S section line
2450 feet from WXX section line
Lease Name Behm A Well # 1
County Morton 78.49
Well Total Depth 2415 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 650

TECHNICIAN'S PLUGGING REPORT
Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name: _____
Address: P.O. Box 351
Liberal, KS 67905-0351

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Big A Drilling LC License Number 31572
Address: P.O. Box 1856, Liberal, KS 67905-1856

Company to plug at: Hour: 11 p.m. Day: 30 Month: 9 Year: 19 95

Plugging proposal received from Jim Barlow
(company name) Anadarko Petroleum Corp. (phone) 316-624-6253

work: to fill hole with heavy mud and spot cement through drill pipe
1st plug at Base Anhydrite with 50 sx cement, 2nd plug at 690' with 50 sx cement;
3rd plug at 40-0' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by _____

RECEIVED
STATE CORPORATION COMMISSION
Steve Dupont
(TECHNICIAN)
OCT - 4 1995
None
CONSERVATION DIVISION
10 Wichita, Kansas 95

Plugging Operations attended by Agent?: All _____ Part _____

Operations Completed: Hour: 1 a.m. Day: 1 Month: _____

ACTUAL PLUGGING REPORT 1st plug at 1490' with 50 sx cement,
2nd plug at 690' with 50 sx cement,
3rd plug at 40-0' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED

do not observe this plugging.

DATE 10-17-95
INV. NO. 43792
10-1

Signed Steve Dupont
(TECHNICIAN)

FOR KCC USE:

FORM C-1 7/91

EFFECTIVE DATE: 9-19-95

State of Kansas

15-

FORM MUST BE TYPED

DISTRICT #

NOTICE OF INTENTION TO DRILL 129-21,401-0000

FORM MUST BE SIGNED

SGA? Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well.

ALL BLANKS MUST BE FILLED

Expected Spud Date 9.15.95 month day year

Spot East X West

OPERATOR: License # 4549 Name: ANADARKO PETROLEUM CORPORATION Address: P.O. BOX 351 City/State/Zip: LIBERAL, KANSAS 67905-0351 Contact Person: JIM BARLOW Phone: (316) 624-6253

1390 feet from South/North line of Section 2450 feet from East West line of Section IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

County: MORTON

Lease Name: BEHM "A" Well #: 1

Field Name: HUGOTON

Is this a Prorated/Spaced Field? X yes no

Target Formation(s): CHASE

Nearest lease or unit boundary: 1250'

Ground Surface Elevation: 3400 feet MSL

Water well within one-quarter mile: X yes no

Public water supply well within one mile: X yes no

Depth to bottom of fresh water: 180' (JK)

Depth to bottom of usable water: 480' (JK)

Surface Pipe by Alternate: X 1 2

Length of Surface Pipe Planned to be set: 525'

Length of Conductor pipe required: NONE

Projected Total Depth: 2415'

Formation at Total Depth: CHASE

Water Source for Drilling Operations:

X well farm pond other

(APPLY FOR FROM DWZ)

Will Cores Be Taken? X yes no

If yes, proposed zone:

If OWWO: old well information as follows:

Operator:

Well Name:

Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? X yes no

If yes, true vertical depth:

Bottom Hole Location:

Exp. 3/14/96

500' Alt. I RABBITDAVIT

EXCEPTION TO CONTIGUOUS ACREAGE

DOCKET No. 191,908-C (C-1 RECEIVED)

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well and its completion, et. seq.

It is agreed that the following minimum requirements will be met:

SFP 14 1995

Pusher: Jim Barlow
SPUD DATE: 9/23/95
LENGTH SURFACE PLANNED: 600'
RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE @ CONDUCTOR ANHYDRITE T- B- ELEVATION
TD 2415 FORMATION ch
RAN PIPE @ DV TOOL ALT II DONE SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
Base Anhydrite Base @ 1490 Ft. W/ 50 SX
1/2 Base Anyh. @ Ft. W/ SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ 690 Ft. W/ 50 SX
40' Plug @ 40-0 Ft. W/ 10 SX
RAT HOLE CIRC/W/ SX MOUSE HOLE W/ 10 SX
WATER WELL SX (Irr. Well Pond Hauling X)
TECHNICIAN SD DATE 9/29/95
TYPE OF CEMENT 60/40 60/6 g.c.t.
STARTING TIME 11:00 (AM/PM) DATE 9-30-95
COMPLETION TIME 1:00 (AM/PM) DATE 10-1-95
CEMENT COMPANY