

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-00228-00-00  
Spot: SWNWSE Sec/Twnshp/Rge: 8-32S-40W  
1790 feet from S Section Line, 2440 feet from E Section Line  
Lease/Unit Name: KINSLER B Well Number: 1  
County: MORTON Total Vertical Depth: 2316 feet

Operator License No.: 5952  
Op Name: BP AMERICA PRODUCTION COMPANY  
Address: 2225 WEST OKLAHOMA AVENUE  
ULYSSES, KS 67880

Conductor Pipe: Size feet: 8 75.27  
Surface Casing: Size 10.75 feet: 372 WITH 250 SX CMT  
Production: Size 7 feet: 2183 WITH 125 SX CMT  
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 04/03/2002 9:00 AM  
Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES  
Proposal Rcvd. from: SPANKY SPOHN Company: BP AMERICA Phone: (316) 356-6955

Proposed Plugging Method: CIBP @ 1500' WITH 7 SX CMT. PERFORATE AT 690' & ESTABLISH CIRCULATION. PUMP CMT DOWN CASING.

Plugging Proposal Received By: STEVE DURRANT WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 04/03/2002 3:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

SLOTTED 5 1/2" LINER SET AT 2170-2316'. CIBP @ 1500' WITH 7 SX CMT. TEST CASING TO 300#. PUMP MUD PLUG TO 690'. PERFORATE AT 690'. ESTABLISH CIRCULATION & PUMP 220 SX CMT DOWN 7". DID NOT SEE CMT AT SURFACE. SENT FOR MORE CMT. PUMP CMT DOWN CASING. GOOD CIRCULATION. NO CMT TO SURFACE. LEFT 7" CASING FULL AT 150 PSIG. HOOKED ONTO 1" & PUMPED 55 SX CMT. PRESSURED TO 300 PSIG. SHUT IN.

RECEIVED  
KANSAS CORPORATION COMMISSION  
APR - 9 2002  
CONSERVATION DIVISION

Remarks: USED 60/40 POZMIX 6% GEL BY HALLIBURTON. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Jim Holland PART II  
(TECHNICIAN)

INVOICED  
DATE 4-10-02 APR 04 2002  
INV. NO. 2002061647 NP

FORM 23