

To: 1 020690 6-16
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-129-00234-0000
SW SW SW SW, SEC. 14, T. 32 S, R. 40 W X

TECHNICIAN'S PLUGGING REPORT

Operator License # 5952
Operator: Amoco Production Company
Name & Address: P.O. Box 800
Denver, CO 80201

150 feet from S section line
150 feet from W X section line
Lease Name Kelly GU "A" Well # 1
County Morton
Well Total Depth 2612 84.89 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 639

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Dowell License Number _____
Address Ulysses, KS

Company to plug at: Hour: 8 a.m. Day: 16 Month: 6 Year: 19 93

Plugging proposal received from Melanie Hill

(company name) Amoco Production Co. (phone) 316-356-1237

were: 6" at 2600', Perfs at 2403-2609', sanded in to 1500'
1st plug at 1500' with 40 sx cement through tubing
2nd plug circulate 75 sx cement down 6" through hole at 850', circulate back to surface up
the 10 3/4" X 6" annulus.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 5 p.m. Day: 16 Month: 6 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 1500' with 40 sx cement through tubing,
2nd plug circulated 75 sx cement down 6" through hole at 850'. Circulated back to surface
up the 10 3/4" X 6" annulus.

Remarks: Used Class C cement by Dowell. No casing recovery.

RECEIVED STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this form.)

INVOICED (if not, observe this plugging.)

DATE 7-21-93
INV. NO. 38177

Signed Glenn R. Barlow (TECHNICIAN) JUL 20 1993 CONSERVATION DIVISION Kansas