

To: 1 051966
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5952
Operator: Amoco Production Company
Name:
Address: P.O. Box 800, Room 924
Denver, CO 80201

9-11
API NUMBER 15-129-20,451-0000
C NE SW, SEC. 19, T 32 S, R 40 W/EX
1980 feet from S section line
3300 feet from E section line
Lease Name Fortenbaugh Gas Unit
County Morton Well # 1
91.00
Well Total Depth 2800 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 682

Abandoned Oil Well Gas Well ☒ Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Halliburton License Number
Address:

Company to plug at: Hour: 11 a.m. Day: 11 Month: 9 Year: 19 95

Plugging proposal received from Bill Chaworth
(company name) Amoco Production Company (phone) 316-356-8102

were: 5 1/2" at 2799' w/550 sx cement, PBTD 2761', Perfs at 2554-2663'

1st plug pump down 5 1/2" casing with 275 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part None

Operations Completed: Hour: 12:30 p.m. Day: 11 Month: 9 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug pumped down 5 1/2" casing with 275 sx cement.

Maximum pressure 180 psi and shut in 180 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery. 5 1/2" casing circulated.

(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 9-21-95
INV. NO. 43553
observe this plugging.

Signed Richard W. Lacy
(TECHNICIAN)