

To: 1 020695 8-11  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-129-21,056-0000  
E/2 SE, SEC. 19, T. 32 S, R. 40 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5703  
Operator: J.M. Huber Corporation  
Name & Address: 7120 I-40 West, Ste. 100  
Amarillo, TX 79106

1320 feet from S section line  
660 feet from E section line  
Lease Name Fortenbaugh Well # 19-2  
County Morton  
Well Total Depth 5610 182.32 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1704

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor J.M. Huber License Number 5703  
Address P.O. Box 888, Spearman, TX 79081

Company to plug at: Hour: 11:45 a.m. Day: 11 Month: 8 Year: 1993

Plugging proposal received from Don Cummings  
(company name) J.M. Huber (phone) 316-353-8395

was: 5 1/2" at 5608' w/355 sx cement, PBTD 5250', Perfs at 5214-24, 5390-5412', CIBP at 5450'  
DV @ 3407' w/380 sx cement 5472-80'

1st plug set CIBP at 5175' with 2 sx cement,  
2nd plug shoot pipe, run tubing to 1710' and pump 50 sx cement,  
3rd plug pull to 700' and pump 40 sx cement, 4th plug pull to 40' and pump 10 sx cement to 0'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 5 p.m. Day: 11 Month: 8 Year: 1993

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5175' with 2 sx cement on top,  
Shot pipe at 1050', still in cement,

2nd plug ran tubing to 1710' and pumped 50 sx cement,  
3rd plug pulled to 700' and pumped 40 sx cement,  
4th plug pulled to 40' and pumped 10 sx cement to surface.

Displaced all plugs with mud.

Remarks: Used Class C cement by Halliburton. Recovered 700' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 17 1993

INVOICED  
I (did / did not) observe this plugging.

DATE AUG 18 1993

Signed Glenn R. Barlow (TECHNICIAN)

INV. NO. 38377