

1 020025

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-129-00075-0000

NE SW, SEC. 24, T 32 S, R 40 W/EX

1980 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5952

Lease Name Bonham G.U. Well # B-1

Operator: Amoco Production Company
Name &

County Morton 195.00

Address P.O. Box 432

Well Total Depth 6000 feet

Liberal, KS 67901

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 705

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pulling License Number 6497

Address Box F, Sublette, KS 67877

Company to plug at: Hour: 1:30 p.m. Day: 4 Month: 9 Year: 19 86

Plugging proposal received from Ed Eaves

(company name) Midwest Casing Pulling (phone) 316-675-8349

were: 4 1/2" at 5964' PBSD 5964 Perfs at 5815-17, 5853-55, 5798-5822'

1st plug set cast iron bridge plug @ 5700' and dump 2 sx cement on top of sand through bailer.

2nd plug fill hole with heavy mud and pump 50 sx cement @ 1020' pumped through 4 1/2" production pipe, 3rd plug at 755' with 75 sx cement pumped through 4 1/2", 4th plug 40-0' with 10 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 5 Month: 9 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug set cast iron bridge plug @ 5690' with 2 sx cement dumped on top of sand through bailer, 2nd plug hole loaded - ran 50 sx cement at 1030'

3rd plug @ 655' with 75 sx cement, 4th plug at 40-0' with 10 sx cement.

Cut off 4' below GL and welded cap on.

Remarks: Common cement by Midwest Casing Pulling was used. Recovered 1050' of 4 1/2".
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE SEP 10 1986

SEP 9 1986

Signed [Signature]
(TECHNICIAN)

INV. NO. 14908