

1 020396

8-30

353R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 129-21,059-0000

SW NW, SEC. 28, T. 32 S, R. 40 WXX
3300 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3871

Lease Name Bowker Well # 1-28

Operator: Hugoton Energy Corp.

County Morton 188.50

Name & Address 229 E. William, Suite 500

Well Total Depth 5800 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1583

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Midwest Casing Pulling License Number 6497

Address Box F, Sublette, KS 67877

Company to plug at: Hour: 3 p.m. Day: 28 Month: 8 Year: 19 91

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling (phone) 316-675-8349

were: 4 1/2" at 5635' w/1150 sx cement, PBTD 5570', Perfs at 5477-87'

1st plug pump 2 sx hulls and 20 sx cement over perfs,

2nd plug pump 50 sx cement at 1600',

3rd plug pump 40 sx cement at 750',

4th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2 p.m. Day: 30 Month: 8 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement at perfs, pressure 1000#,

2nd plug pumped 50 sx cement at 1600',

3rd plug pumped 40 sx cement at 750',

4th plug pumped 10 sx cement at 40-0'.

All plugs displaced with mud.

RECEIVED
STATE CORPORATION COMMISSION

SEP 05 1991

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Midwest Casing Pulling. Recovered 1923' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 9-12-91

Signed Glenn R Barlow (TECHNICIAN)

33105