

To: 1020865 5-18
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-129-21,254-0000
C E/2 SE, SEC. 30, T. 32 S, R. 40 W/E
1320 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3871
Operator: Hugoton Energy Corporation
Name & Address 301 N. Main, Ste. 1900
Wichita, KS 67202

Lease Name Krey Well # 3-30
County Morton
Well Total Depth 5800 188.50 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1946

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 3 p.m. Day: 17 Month: 5 Year: 1995

Plugging proposal received from Richard McIntyre
(company name) Mike's Testing & Salvage Inc. (phone) 316-938-2943

were: 4 1/2" at 5642' w/100 sx cement, Perfs at 5234-37, 5304-18, 5496-5500, 5506-24'
1st plug pump 2 sx hulls and 40 sx common cement,
2nd plug pump 100 sx cement at 2750', 3rd plug pump 50 sx cement at 1980',
4th plug pump 40 sx cement at 650',
5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 18 Month: 5 Year: 1995

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 40 sx cement at perfs, displaced to 5100' with 700#,

2nd plug pumped 100 sx cement at 2750',
3rd plug pumped 50 sx cement at 1980',
4th plug pumped 40 sx cement at 650',
5th plug pumped 10 sx cement at 40-0'. Displaced all plugs with fresh water.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2914' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED
DATE JUN 13 1995
INV. NO. 42950

Signed [Signature]
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
5-25-95 MAY 25 1995
CONSERVATION DIVISION
WICHITA, KANSAS