

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-175-20,728-0000

NW NW, Sec. 35, T 32 S, R 34 W/E

660 feet from N/S section line

660 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Lease Name Federal Land Bank Well # 1

Operator: Petroleum, Inc
Name & Address 800 R.H. Garvey Bldg.
300 West Douglas
Wichita, Kansas 67202

County Seward

Well Total Depth 6335 feet 205.88

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1635

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor NRG Drilling Inc License Number 6066

Address Box 1157 Liberal, Kansas 67901

Company to plug at: Hour: 4:00am Day: 11 Month: January Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Steve Phelps

(company name) Petroleum Inc (phone)

were: Fill hole with heavy mud + spot plugs + through drill pipe
1st plug @ 3170' w/50sx, 2nd plug @ 2550' w/50sx
3rd plug @ 1680' w/50sx, 4th plug @ 750' w/40sx
5th plug @ 40' w/solid Bridge plug + 10sx, Circulate
10sx in the Rathole, Circulate 10sx in the mousehole
Using 60/40 poz mix Signed Richard M. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:30am Day: 11 Month: January Year: 1984

ACTUAL PLUGGING REPORT Fill hole with heavy mud + spot plugs through pipe
1st plug @ 3170' w/50sx, 2nd plug @ 2550' w/50sx,
3rd plug @ 1680' w/50sx, 4th plug @ 750' w/40sx
5th plug @ 40' w/solid Bridge plug + 10sx, Circulate
10sx in the Rathole, Circulate 10sx in the mousehole
Using 60/40 poz mix

Remarks: Halliburton pumped the cement

I hereby certify that the above plugging instructions were given as herein stated and that I (~~did~~ / did not) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION

JAN 18 1984

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 1-20-84

INV. NO. 9211 W

Signed Richard M. Lacey
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82