

To: 1 100091 1-22
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 119-20,968-0000
SE SW, SEC. 18, T 32 S, R 29 W/E
660 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address: P.O. Box 351
Liberal, KS 67905-0351

Lease Name Pearson B Well # 1
County Meade 199, 87
Well Total Depth 6150 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1628

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: _____ Day: 21 Month: 1 Year: 19 97

Plugging proposal received from Don Horton
(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

Work: 5 1/2" at 5300', PBTD 5250', Perfs at 5132-40', TOC @ 4800'
1st plug pump 2 sx hulls and 25 sx cement at 5152-4932',
2nd plug pump 50 sx cement at 1678',
3rd plug pump 40 sx cement at 650',
4th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Gary Winters (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 3:30 p.m. Day: 22 Month: 1 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement from 5132-5032',
2nd plug pumped 40 sx cement at 3100-3000',
3rd plug spotted 50 sx cement at 1678',
4th plug spotted 40 sx cement at 650',
5th plug at 40-0' with 10 sx cement.

Remarks: Used common cement by Sargent & Horton. Recovered 3135' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (CARD) EXPOSED Reserve this plugging.

DATE 1-29-97
INV. NO. 47489

Signed Gary Winters (TECHNICIAN)

RECEIVED
MILLS & BOSS
CORP
JUL 29 1997