

1031563

TO: STATE CORPORATION COMMISSION

API NUMBER 15-119-20,576-0000  
W/2 SW SE SEC. 21, T 32 S, R 29 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME SCHRIDDE WELL # 1

TECHNICIAN'S PLUGGING REPORT 8/15 COUNTY MEADE 186.39

OPERATOR LICENSE # 4951 WELL TOTAL DEPTH 5735 FEET

OPERATOR: CLAASSEN OIL & GAS INC. PRODUCTION CSG: SIZE 4 1/2" @ 5734' WITH 150 SX

NAME AND PO BOX 417 SURFACE CASING: SIZE 8 5/8" @ 1533' WITH 700 SX

ADDRESS ESTES PARK, CO 80517

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC LICENSE NUMBER 31151

ADDRESS RT. 1, BOX 49BA, TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 12:30 PM DAY: 14 MONTH: 08 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT & HORTON PLUGGING, INC (PHONE) 580-854-6515

WERE: PERFS AT 5631-35, 5618-20, 5592-96, 5458-64.. CIBP @ 5626

1ST PLUG PUMP 20 SX CEMENT AND 1 SX HULLS IN BOTTOM. 2ND PLUG AT 1560' WITH 50 SX CEMENT.

3RD PLUG AT 600' WITH 40 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  NONE

OPERATIONS COMPLETED: HOUR: 10:00 AM DAY: 15 MONTH: 08 YEAR: 2000

ACTUAL PLUGGING REPORT \_\_\_\_\_

1ST PLUG PUMP 20 SX CEMENT AND 1 SX HULLS ON BOTTOM. 2ND PLUG AT 1560' WITH 50 SX CEMENT.

3RD PLUG AT 600' WITH 40 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT. RECEIVED KANSAS CORPORATION COMMISSION

AUG 16 2000

CONSERVATION DIVISION  
WICHITA, KS

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 2500' OF 4 1/2" CASING.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED  
DATE 8/18/00  
WV. NO. 1060434

SIGNED Steve Purvitt  
(TECHNICIAN) FORM CP-2/3

AWB