

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Sumner

County. Sec. 4 Typ. 32 Rge. 1W (E) (W)

Location as "NE/CNW/SW" or footage from lines. NW SW SW

Lease Owner CRA, Inc.

Lease Name Deturk B Well No. 21

Office Address Box 98 Wellington, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil Well

Date well completed 19

Application for plugging filed 3-10-67 19

Application for plugging approved 3-13-67 19

Plugging commenced 3-30-67 19

Plugging completed 4-1-67 19

Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes Howard Hess

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top: Bottom: Total Depth of Well 3680 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	116'	none
				5 1/2	3658	2710'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill hole from 3680' to 3640' with chat and dump 4 sacks of cement

Set 15' rock bridge from 240' to 225' and dump 4 1/2 cubic yards of ready mix concrete

RECEIVED
STATE CORPORATION COMMISSION

APR 17 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Flint Engineering and Const. Co.
Address 2375 W. Central El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *[Handwritten Signature]*

(Address)

SUBSCRIBED AND SWORN to before me this 12 day of April, 19 67

[Handwritten Signature]

My commission expires Sept. 27, 1967

Notary Public.

S.S. Strider

15-191-01223-0000

KANSAS WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY LAURA JANE OIL CO., INC.

SEC. 4 T. 32 R. 17

LOC. NW SW SW

FARM DeTurk "B"

NO. 2

COUNTY Sumner

TOTAL DEPTH 3680

COMM. 1-23-51


COMP. 2-4-51

SHOT OR TREATED

CONTRACTOR Laura Jane Oil Co.

ISSUED 5-19-51

KANSAS



CASINO

8 5/8" 116'
5 1/2" 3658'

ELEVATION 1224 D.F.

PRODUCTION May. 25 bbls.

FIGURES INDICATE BOTTOM OF FORMATIONS

soil	30
sand	75
shale	135
lime, shale	1140
shale, shells	1680
shale, lime	1730
shale, shells	2030
lime	2140
shale, lime	2665
sand	2765
lime, shale	2995
lime	3270
shale, lime	3300
lime sdy	3330
shale, lime	3647
chat	3658 RTD
chat	3680
Total Depth	

Tops:
Mississippi 3647

RECEIVED
STATE CORPORATION COMMISSIONER
MAR 13 1967
CONSERVATION DIVISION
Wichita, Kansas