

15-189-00031-0001

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER None
LEASE NAME Kelly B
WELL NUMBER 1A
3960 Ft. from S Section Line
3960 Ft. from E Section Line
SEC. 15 TWP. 34S RGE. 38 (W)
COUNTY Stevens
Date Well Completed 3-15-79
Plugging Commenced 4-15-88
Plugging Completed 4-16-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company
ADDRESS P.O. Box 21468
PHONE# (918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well SWD
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on N/A (date)
by N/A (KCC District Agent's Name).

Is ACO-1 filed? on old form if not, is well log attached? --
Producing Formation None Depth to Top -- Bottom -- T.D. 6590

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Anhydrite	water	1769	2200	13 3/8	599	-0-
				8 5/8	1769	-0-
				4 1/2	3135	2210 (in 1979)

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pumped a 100 sxs cmt plug from 1755' - 2138'. Pumped a 50 sx cmt plug from 615' - 515'. Set top plug w/10 sxs cmt from 30' - 4'. (Pumped 200 sxs cl 'H' down annulus from 510'-4'.)
Welded on plate w/name & date. (Original PBD @ 2210')
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1988
6568
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Kaiser-Francis Oil Company License 6568
Address P.O. Box 21468 Tulsa, OK. 74121-1468
STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg
(Address) P.O. Box 21468

SUBSCRIBED AND SWORN TO before me this 17th day of May, 19 88

My Commission Expires: 6-25-90 Notary Public