

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Finney State Office Building  
130 South Market, Rm 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-129-00259-0000

LEASE NAME BLUCHER

WELL NUMBER 1-34

2800 Ft. from N Section Line

2440 Ft. from W Section Line

SEC. 34 TWP. 32S RGE 40 (E) or (W)

COUNTY MORTON

Date Well Completed 06/13/57

Plugging Commenced 03/08/97

Plugging Completed 03/10/97

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # ( 316 ) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 02/24/97 (date)

by MR. STEVE PFEIFER (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation CHASE Depth to Top 2244' Bottom 2397' T.D. 2397'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
CHASE	GAS	2244'	2397'	10-3/4"	416'	3'
				7"	2244'	3'
				5-1/2"	2397'	0'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from     feet to     feet each set, MIRU SARGENT & HORTON PLUGGING, INC. MIRU WL. SET CIBP @ 2100'. DMP 2 SXS CMT ON CIBP. PERF 466-467' W/4 SPF & 90 DEG PHASING. LD HOLE W/9 PPG MUD. PMP 100 SXS CLASS "H" CMT PLG FROM 266 TO 466'. CUT OFF 10-3/4" & 7" CSG 3' BELOW GL. PMPD 15 SXS CMT PLG FROM 40-3' AND CAP & INSCRIBE. NOTIFIED KCC REP STEVE PFEIFER ON 3/10/97

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT. 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE: (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John A. Broman


JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 21st day of May, 1997

Shirley J. Childers  
Notary Public

My Commission Expires: 11/14/98



KANSAS RECEIVED  
1997 MAY 22