

15-025-20162-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Clark County, Sec. 24 Twp. 31S Rge. 21 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C NE NW

Lease Owner Reading & Bates Oil and Gas Co.
Lease Name Berryman Well No. 1
Office Address 3800 First Place, Tulsa, Okla. 74103
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Dry Hole
Date Well completed October 13 1977
Application for plugging filed November 9 1977
Application for plugging approved November 14 1977
Plugging commenced December 13 1977
Plugging completed December 16 1977

Reason for abandonment of well or producing formation
Dry Hole -
If a producing well is abandoned, date of last production
No Production - Dry Hole 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas
Producing formation - Depth to top - Bottom - Total Depth of Well 5303'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Red Bed	Fresh water	0	150'	16"	60'	-0-
Morrow Sd.	Salt water	5140'	5149'	4 $\frac{1}{2}$ "	676'	-0-
Mississippian	Salt water	5150'	5303'	4 $\frac{1}{2}$ "	5298'	3457'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from - feet to - feet for each plug set. C.I. Bridge plug set @ 5162'.

Pump 15 sx. cmt. plug to 5000' w/mud laden fluid.

Pipe was shot free @ 3438' and pulled.

60 sx. cmt. plug was pumped from 744-564'.

Capped well w/10 sx. cmt. and welded steel plate.

RECEIVED
STATE CORPORATION COMMISSION

DEC 23 1977

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Jerry Reeves, Inc.

STATE OF Oklahoma COUNTY OF Tulsa, ss.
Reading & Bates Oil and Gas Co. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Glenn E. Wood
3800 First Place, Tulsa, Okla. 74103

(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of December, 1977

Virginia Barksdale
Notary Public.

My commission expires November 16, 1978