

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD 15-007-30197-0000

Barber County, Sec. 22 Twp. 31S Rge. 13W (E) (W)

Location as "NE/CNW&SW" or footage from lines G-NE $\frac{1}{4}$ -NW $\frac{3}{4}$

Lease Owner Sunray DX Oil Company

Lease Name Ernest McGuire Well No. 1

Office Address 300 Union National Building Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 12-19 19 65

Application for plugging filed 12-20 19 65

Application for plugging approved 12-20 19 65

Plugging commenced 12-19 19 65

Plugging completed 12-19 19 65

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH

	X		

Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elving

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3813 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUR IN	PULLED OUT
Lansing	Dry	3771	Td	13 3/8	288	0
Douglas	Dry	3751	3759			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mud from 3813' to 275'  
50 sacks cement plug from 275' to 110'  
30 sacks cement plug from 110' to surface  
5 sacks cement in rat hole

RECEIVED  
STATE CORPORATION COMMISSION

DEC 27 1965

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stickle Drilling Company

Address 1100 Bitting Bldg. Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

V.A. Tracy (employee of owner) or (owner and operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V.A. Tracy

300 Union National Bldg. Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of December, 19 65

My commission expires March 28, 1969

Mae Resco  
MAE RESCO Notary Public.

Sunray DX Oil Company  
Wichita, Kansas

22 December 1965  
Wichita, Kansas

Drlg Contractor: Stickle Drlg. Company  
Date Commenced: 12 December 1965  
Date Completed: 19 December 1965

Ernest McGuire #1  
NE NW 22-31-13W  
Barber County, Kansas


DRILLER'S LOG

15-067-30197-0000

Depth figures indicate base of formation:

Surface clay and shale	399
Shale	1350
Shale and lime	1861
Lime and shale	2160
Lime	2225
Lime and shale	2337
Shale and lime	2555
Lime and shale	2651
Shale and lime	2906
Lime and shale	3140
Shale and lime	3472
Lime and shale	3780
Lime	3813 TD

I, Clifford Smith, hereby certify that to the best of my knowledge and belief, the above is a true and complete Driller's Log of the Ernest McGuire No. 1, NE NW 22-31-13W, Barber County, Kansas.

  
Clifford M. Smith

  
Wanda J. Steakley  
My Commission Expires 16 January 1966.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 27 1965

CONSERVATION DIVISION  
Wichita, Kansas