

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-607-22056-0000

LEASE NAME Packard

WELL NUMBER #4

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

         Ft. from S Section Line

         Ft. from E Section Line  
50' East, W/2 NE NE

SEC. 22 TWP. 31 SRGE. 13 (E) or (W)

COUNTY Barber

Date Well Completed 1-18-86

Plugging Commenced 4-21-88

Plugging Completed 6-15-88

LEASE OPERATOR Mid-Continent Energy Corporation

155 N. Market, Suite 200

ADDRESS Wichita, Kansas 67202-1816

PHONE # (316) 265-9501 OPERATORS LICENSE NO. 5205

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filled?          if not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 4487'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	220'	none
				4-1/2"	4486'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set.

Pumped 1 Hull and 30 sacks cement, well went on a hard vaccum. Plug went 10' past perfs to 4465'. Displaced casing W/60 barrels water.

Pumped 5 hulls and 30 sacks cement, plug stopped @3550'. Shot pipe @3120', 701', closed casing and surface back in. Pumped 80 sacks cement, 60/40 pos.,

(If additional description is necessary, use BACK of this form.) 6% gel, down 4-1/2" casing. Plugging

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050 Complete

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

STATE CORPORATION COMMISSION

(Signature) R. Darrell Kelso

Box 347

(Address) Chase, Kansas 67524


JUN 23 1988

SUBSCRIBED AND SWORN TO before me this 21st day of June, 19 88

CONSERVATION DIVISION  
 Wichita, Kansas

James Hoover  
 Notary Public

My Commission Expires:         



KCC OIL/GAS REGULATORY OFFICE

15-007-22056-0000

DATE 6/15/88

- New Situation
- Response to Request
- Follow-up

OPERATOR Mid-Continent Energy Corp. # 5205

150' E of  
LOCATION W/2 NE NE, SEC 22, T 31 S, R 13

NAME & ADDRESS 155 North Market, Suite 200

Wichita, KS 67202-1816

LEASE Packard Well # 4

PHONE NO. OPER. OTHER

COUNTY Barber

REASON FOR INVESTIGATION: ~~Add no charge by record form.~~

LEASE INSPECTION

PROBLEM:

PERSON(S) CONTACTED:

FINDINGS: Pumped into 4 1/2" X 8 5/8" annulus. Pressured to 1000 psi and broke back to 500 psi.

Established injection rate at 4 BPM at 500 psi. Pumped down annulus with 80

sy cement. Maximum pressure 1000 psi and shut in 800 psi.

Start time 1:15 p.m. and completion time 1:30 p.m. on 6/15/88.

Used 60/40 Pozmix 6% gel by B.J. Titan.

COMPLAINT

RECEIVED  
STATE CORPORATION COMMISSION

JUN 22 1988

CONSERVATION DIVISION  
Wichita, Kansas

photos taken:

ACTION/RECOMMENDATIONS:

FIELD REPORT

Retain 1 copy Joint District Office  
Send 1 copy Conservation Division

By Stephen J. Pfeifer