


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

15-007-20094-0000

NORTH



Locate well correctly on above
Section Plat

Barber County, Sec. 26 Twp. 31S Rge. (E) 13 (W)
Location as "NE/CNW/SE/SW" or footage from lines. C SW SW
Lease Owner. Tilco, et al
Lease Name Stonestreet Well No. 1
Office Address 815 Wichita Plaza Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4-11 1969
Application for plugging filed 4-11 1969
Application for plugging approved 4-11 1969
Plugging commenced 4-11 1969
Plugging completed 4-11 1969
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4220 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13"	202'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged with 50 sacks cement mud to 30' 1 sack hulls plug 20 sacks
cement 2 sacks cement in rat hole

RECEIVED
STATE CORPORATION COMMISSION
APR 15 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

(Address) _____

SUBSCRIBED AND SWORN to before me this 14th day of April, 1969

My commission expires April 1, 1971

Ulanda Nichols
Ulanda Nichols Notary Public.

DRILLER'S LOG

15-007-20094-000

COMPANY Tilco, et al
 CONTRACTOR LEBEN DRILLING, INC.
 FARM STONESTREET #1
 LOCATION C SW SW SECTION 26-31S-13W
 BARBER COUNTY, KANSAS
 COMMENCED 4-1-69
 COMPLETED 4-11-69

0	20	Sand
20	900	Red Bed
900	1363	Red Bed, Shale
1363	1550	Anhydrite
1550	1755	Lime, Shale
1755	2545	Lime
2545	2570	Lime, Shale
2570	2630	Sand, Shale
2630	2890	Shale, Lime
2890	3115	Lime, Shale
3115	3500	Lime
3500	3620	Shale, Sand
3620	3690	Sand
3690	4211	Lime
4211	4220	Lime, Chert
	<u>4220</u>	<u>RTD - D. & A.</u>

RECEIVED
 STATE CORPORATION COMMISSION
 APR 15 1969
 CONSERVATION DIVISION
 Wichita, Kansas

13" surface casing set @ 202' cemented with 225 sacks Sunset cement

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Stonestreet #1 Well, located C SW SW of Section 26, Township 31 South, Range 13 West, Barber County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 14th day of April, 1969.

Clarence D. ...

My Commission Expires:
April 1, 1971