

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

15-607-2096-0000

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Barber County, Sec. 26 Twp. 31<sup>25</sup> Rge. 13 W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

660 FSL 666 FWL  
Lease Owner Texas Oil and Gas Corporation  
Lease Name Catlin Well No. B-1  
Office Address Suite 300 - 200 W. Douglas  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above Section Plot

Oil  
Date Well completed Sept. 23 19 80  
Application for plugging filed Dec. 14 19 81  
Application for plugging approved Dec. 16 19 81  
Plugging commenced Dec. 22 19 81  
Plugging completed Jan. 4 12:30 19 82  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. V. Leslie  
Producing formation Depth to top Bottom Total Depth of Well 4,275  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	329	None
				4 1/2	4,274	3,630

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Dump sand cover perforation.  
Dumped 4 sacks cement with dump bailer.  
Halliburton pumped in 15 jell - 8 hull - 10-jell.;  
150 sacks common cement - 2% jell - 3% c.c.

RECEIVED  
STATE CORPORATION COMMISSION  
1-7-82  
JAN 7 1982  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Clarke Corporation

STATE OF Kansas COUNTY OF Barber, ss.  
Elmer R. Morgenstern (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Elmer R. Morgenstern  
Medicine Lodge, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of January, 1982.

Jessie Hamilton  
Notary Public.

My commission expires April 4, 1982.

KANSAS DRILLERS LOG

COMPANY Texas Oil & Gas Corp.  
FARM Catlin "B" NO. 1

SEC. 26 T. 31S R. 13W  
LOC. 660' FSL & 660' FEL

COUNTY Barber

ROTARY TOTAL DEPTH 4,275'  
COMM. September 5, 1980 COMP. September 12, 1980  
CONTRACTOR H-30, INC. (Rig #5)  
ISSUED September 23, 1980

CASING

10 3/4"  
8 5/8" Set at 329' cemented w/300 sxs cement  
5 1/2"  
4 1/2" Set at 4,274' cemented w/150 sxs cement

ELEVATION 1,531' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Red Bed and Sand	347'
Sand and Red Bed	909'
Red Bed and Shale	1,782'
Shale and Lime	4,275'
Rotary Total Depth	4,275'

I hereby certify the above and foregoing to be  
a true and correct log of the above described  
well as shown by the drilling reports.

H-30, INC.

*Dean Britting*  
Dean Britting

State of Kansas )  
                          ) SS:  
County of Sedgwick )

Subscribed and Sworn to before me a Notary Public  
in and for said county and state this 23rd day of  
September, 1980.

*Elsie Willison*  
Elsie Willison - Notary Public

My Commission Expires:  
July 25, 1982

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 10 1980  
CONSERVATION DIVISION  
Wichita Kansas