

15-007-60044-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Barber County. Sec. 28 Twp. 31 Rge. (E) 13 (W)

Location as "NE/CNW%SW%" or footage from lines C SE/4 NW/4

Lease Owner Colorado Oil & Gas Corporation

Lease Name HARTLEY Well No. 1

Office Address Box 1030 Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed January 5, 19 61

Application for plugging filed January 5, 19 61

Application for plugging approved January 5, 19 61


Plugging commenced January 5, 19 61

Plugging completed January 5, 19 61

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4713 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8-5/8" | 294'   | None       |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with mud to 275'

Plug @ 275' w/20 sacks cement

Filled hole with mud to 35'

Plug @ 35' w/10 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 20 1961  
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Prime Drilling Company

Address 814 Union Center Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Bill K. Henrichs (employee of owner) or (owner/representative) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill K. Henrichs

Box 1030, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 19 day of January, 19 61

My commission expires August 19, 1963

Helen L. Martin  
Helen L. Martin Notary Public.



ROTARY DRILLING LOG

15-007-00044-0000

OPERATOR: Colorado Oil & Gas Corporation  
 HARTLEY No. 1  
 C SE NW Sec. 28-319-13W,  
 Barber County, Kansas

CONTRACTOR: Prime Drilling Company  
 COM: 12-15-60  
 COMPLETED: 1-5-61

Remarks: Set 8-5/8" surface casing  
 at 294' cemented with 250  
 sacks cement, 3 AC-4CC

Formations:

|                          |       |
|--------------------------|-------|
| Sand                     | 60'   |
| Red Bed                  | 460'  |
| Shale & Shells           | 1250' |
| Shale & Lime             | 1600' |
| Lime & Shale             | 1850' |
| Lime                     | 2400' |
| Shale & Lime             | 2810' |
| Lime & Shale             | 3010' |
| Shale & Lime             | 3135' |
| Lime & Shale             | 3225' |
| Shale                    | 3290' |
| Lime & Shale             | 3415' |
| Lime                     | 3590' |
| Lime, Shale & Sand       | 3675' |
| Sand                     | 3726' |
| Lime                     | 4234' |
| Cherty Lime              | 4246' |
| Chert                    | 4292' |
| Cherty Lime Shale        | 4325' |
| Chert                    | 4362' |
| Cherty Lime              | 4398' |
| Lime & Shale             | 4431' |
| Shale                    | 4477' |
| Lime                     | 4515' |
| Cherty Lime              | 4570' |
| Lime                     | 4575' |
| Shale & Lime             | 4585' |
| Sand                     | 4628' |
| Shale & Lime             | 4668' |
| Lime                     | 4713' |
| Rotary Total Depth (D&A) | 4713' |

RECORDED  
 STATE CORRELATION COMMISSION

JAN 20 1961

CONSERVATION DIVISION  
 Wichita, Kansas

We certify the above log is true and  
 correct to the best of our knowledge  
 and belief.

PRIME DRILLING COMPANY

*R. R. McNicol*

R. R. McNicol