

15-307-30149-0000


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 N. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 7 Twp. 31S Rge. (E) 12 (W)

Location as "NE/CNW/SW" or footage from lines 50' E of C NW NE
Lease Owner Lario Oil & Gas Company
Lease Name Gress-Winter "A" Well No. 1
Office Address 301 South Market, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed July 8, 19 65
Application for plugging filed February 4, 19 70
Application for plugging approved February 5, 19 70
Plugging commenced February 14, 19 70
Plugging completed February 17, 19 70
Reason for abandonment of well or producing formation Depleted

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production December 19 69
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. Russell Biberstein
Producing formation Douglas Depth to top 3636 Bottom 3642 Total Depth of Well 3705 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"	253	None
				2 1/2"	3714.7	2836.45'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped 15 sacks cement plug from T.D. to 3200'. Mud from 3200' to 240'. Set plug at 240', ready mix cement to base of cellar. Job completed at 12:00 noon 2-17-70.

RECEIVED
STATE CORPORATION COMMISSION
MAR 4 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Oilfield Service, Inc.
Address Medicine Lodge, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. G. R. Kelsey (employee of owner) or (DIRECTOR) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. R. Kelsey, Div. Prod. Supt.
301 S. Market, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of March, 19 70

Frances Leshe Notary Public.

My commission expires July 21, 1970

15-007-304A-0000

LARIO OIL & GAS COMPANY
Gress-Winter "A" No. 1
50' E. of Cen. NW NE Sec. 7-31S-12W
Barber County, Kansas

RECEIVED
STATE CORPORATION COMMISSION
FEB 5 1970
CONSERVATION DIVISION
Wichita, Kansas

Drilling Commenced: 6-29-65
Drilling Completed: 7-8-65
Well Completed: 7-31-65
Drilling Contractor: White & Ellis Drilling, Inc.
Total Depth 3705' K.B.
I.P. - 4-point test 3,700 M.C.F.

Casing Record:

7" 247.30 Set at 253'
Cem. w/ 100 sacks
2 1/2" 3714.70 Set at 3,704'
Cem. w/ 100 sacks

<u>Formation</u>	<u>Depth</u>
Cellar	8
Soil and red rock	65
Red rock	253
Red rock and shale	840
Shale	1620
Lime	2280
Lime & shale	2375
Lime	2940
Shale & lime	3465
Lime	3616
Sand	3705

Geological Tops - K.B. Meas.

Elev.	1701' K.B.
Heebner	3583' (-1882)
Toronto	3598' (-1897)
Douglas Shale	3616' (-1915)
Douglas Sand	3635' (-1934)
Base of Sand	3662' (-1961)
Welex Total Depth	3669' (-1968)
Rotary Total Depth	3705' (-2004)

7-14-65 Welex perforated 10/3636-42' and
4/3647-50'.

7-15-65 Acidized w/ 500 gallons 7½% mud acid.