

15-007-19113-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Barber County. Sec. 7 Twp. 31S Rge. (E) 12 (W)

Location as "NE/CNWxSWx" or footage from lines C-NE/4 SW/4

Lease Owner Union Texas Petroleum Corporation

Lease Name Winter Well No. 1

Office Address 1200 Skirvin Tower Oklahoma City, Oklahoma 73102

Character of Well (completed as Oil, Gas or Dry Hole) Gas

Date well completed 7-20 1964

Application for plugging filed 2-27 1967

Application for plugging approved 2-28 1967

Plugging commenced 3-3 1967

Plugging completed 3-11 1967

Reason for abandonment of well or producing formation Douglas Gas watered out.

If a producing well is abandoned, date of last production *7-20 1964

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH

	X		

Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well A. Elving

Producing formation Douglas Depth to top 3632 Bottom 3636 Total Depth of Well 3792 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Douglas	Gas & Water	3630	3752	8 5/8	202	None
				4 1/2	3911	2500

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set cement plug @ 3565. Pulled 4 1/2" casing. Filled hole with heavy mud. Put chat plug 190' to 200'. Put 25 sack cement to 115'. Mud & sand to 40'. Put 10 sacks cement to 3' feet below surface. Cut of surface pipe & welded steel plate on top.

RECEIVED
STATE CORPORATION COMMISSION
MAR 20 1967
CONSERVATION DIVISION
Wichita, Kansas

*Was not a commercial well. Did not sell any gas.
(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clark Corporation

Address Medicine Lodge Kansas

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.
Grant B. Grumbine, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

1200 Skirvin Tower Oklahoma City, Okla.
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of March, 19 67

My commission expires 3-21-1968

Notary Public.

15-007-19113-0000

W E L L L O G

OPERATOR: Fred & Philip Anschutz
1521 Wichita Plaza
Wichita, Kansas and
Colorado Oil & Gas

CONTRACTOR: Terrel Drilling & Producing
Box 606
Russell, Kansas

LEASE: Winter #1

COMMENCED: July 1, 1964

LOCATION: C NE SW Sec. 7-31S-12W
Barber County, Kansas

COMPLETED: July 10, 1964

DEPTHS & FORMATIONS

Shale	523	Shale & Lime	2405
Red Bed, Shale & Gyp	1210	Lime & Shale	2555
Red Bed & Shale	1600	Lime	2605
Lime & Shale	1890	Lime & Shale	3665
Lime	2232	Shale (R.T.D.)	3792

STATE OF KANSAS)

COUNTY OF RUSSELL) ss...

Joe K. Branum, owner of Terrel Drilling and Producing, being first duly sworn on oath says: "That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct."

Joe K. Branum
Joe K. Branum - TERREL DRILLING & PRODUCING

Subscribed and sworn before me this 11th day of July, 1964.

L. L. Simpson
Notary Public

My Commission Expires December 12, 1966.

RECEIVED
STATE CORPORATION COMMISSION
APR 4 1967
CONSERVATION DIVISION
Wichita, Kansas