

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-22,131-0001

LEASE NAME Elliot

WELL NUMBER B-2

660 Ft. from S Section Line

1775 Ft. from E Section Line

SEC. 2 TWP. 31S RGE. 9 (W)

COUNTY Barber

Date Well Completed _____

Plugging Commenced 2-7-95

Plugging Completed 2-9-95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Day Star Petroleum

ADDRESS 1321 W. 93rd N. Valley Center, KS

PHONE#(316) 755-3523 OPERATORS LICENSE NO. 30931

Character of Well good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-7-95 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation Miss Depth to Top 4376 Bottom 4388 T.D. 4956

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	327	None
				5 1/2	4956	Approx. 3100

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each section. Push 5 1/2 wiper plug to 4350, dump 100 gal sand, fill up at 4270, dump 5sx cement with dump bailer stretch and cut 5 1/2 at 3100, Allied pump 300 hulls, 10 gel, 50 cement, 10 gel, 100 hulls, 8 5/8 wiper plug, 100sx, 60/40, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, Medicine Lodge, KS 67104


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Day Star Petroleum

STATE OF Kansas COUNTY OF Barber, ss. **RECEIVED**
STATE CORPORATION COMMISSION **FEB 17 1995**

Alan Vratil

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) [Handwritten Signature]

(Address) Medicine Lodge, KS 67104

SUBSCRIBED AND SWORN TO before me this 15 day of February, 19 95

[Handwritten Signature]
Notary Public

My Commission Expires: 10/14/98