

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas


WELL PLUGGING RECORD

15-007-20447-0000

Barber County, Sec. 12 Twp. 31S Rge. 12 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW SE
Lease Owner George R. Jones
Lease Name Mott Well No. 1
Office Address 125 N. Market, Suite 1310, Wichita, KS 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-7-76 19__
Application for plugging filed 11-7-76 19__
Application for plugging approved 11-7-76 19__
Plugging commenced 11-7-76 19__
Plugging completed 11-7-76 19__
Reason for abandonment of well or producing formation Negative tests

NORTH



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production -- 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation -- Depth to top -- Bottom -- Total Depth of Well 4670 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface casing				8 5/8"	358.69'	--

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from -- feet to -- feet for each plug set.

35 sacks cement at 360'
14 sacks cement at 40'
5 sacks cement in rathole

RECORDED
STATE CORPORATION COMMISSION
NOV 17 1976
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.
Address 830 Sutton Place, Wichita, KS 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
George R. Jones (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George R. Jones
125 N. Market, Suite 1310, Wichita, KS
(Address)

SUBSCRIBED AND SWORN to before me this 16th day of November, 19 76

My commission expires March 12, 1978

Jeanine ReQua
Notary Public.

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

15-007-20417-0000

Mott #1
 NW-SE Sec 12-31S-12W
 Barber County Kansas

Commenced: 10-26-76

Completed: 11-7-76

OPERATOR: GEORGE R. JONES

Depth		Formation	Remarks
From	to		
0	40	Sand	Ran 9 jts of 28' 8 5/8" csg set @ 361' Cemented w/325 sks Common 3% CC
40	365	Sand-Redbed	
365	1730	Shale	PD @ 1:30 p.m. 10-27-76
1730	1920	Shale-Lime Stks	
1920	2280	Shale-Lime	
2280	2505	Lime	
2505	3395	Shale-Lime	
3395	3565	Lime-Shale	
3565	3598	Shale	
3598	3740	Shale-Lime	
3740	4353	Lime	
4353	4395	Lime-Shale	
4395	4670	Lime	
	4670 - TD		DRY & ABANDONED

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)


I, the undersigned, being duly sworn on oath, state that the above Drillers Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
 JAMES S. SUTTON II

Subscribed and sworn to before me this 11th day of November, 1976.

Elizabeth J. Edwards
 ELIZABETH J. EDWARDS-NOTARY PUBLIC



RECEIVED
 STATE CORPORATION

NOV 17 1976

CORPORATION
 WICHITA, KANSAS