


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Barber County, Sec. 25 Twp. 31S Rge. 12 (E) (W)X  
Location as "NE/CNW/SW" or footage from lines SW SW NE  
Lease Owner Mull Drilling Company, Inc.  
Lease Name George Kisling Well No. 1  
Office Address P. O. Box 393 Ness City, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 1-2-64 19  
Application for plugging approved 1-3-64 19  
Plugging commenced 1-9-64 19  
Plugging completed 1-11-64 19  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving  
Producing formation Depth to top Bottom Total Depth of Well PB 3390 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	125	None
				5 1/2	None	2026

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set up unit. Rigged up jacks. Measured T. D. Sanded to 3360' and 5 sacks of cement. Shot well at 2514'. Working pipe. Shot pipe at 2300'.

Shot pipe at 2010'. Pulling pipe.

Tried to bail down and couldn't. Squeezed well with 15 sacks of mud and 80 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION

APR 14 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.  
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes  
P. O. Box 221 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 13 day of April, 1964

My commission expires May 27, 1964

Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

COPY


Company- PURCELL-MULL DRILLING CO., INC.  
Farm- Kisling No. 1.

SEC. 25 T. 31 R. 12N  
S1 SW NE

15-007-00073-0000

Total Depth. 4308'  
Comm. 12-26-54 Ccmp. 1-10-55  
Shot or Treated.  
Contractor. Purcell-Mull Drlg. Co., Inc.  
Issued. 3-26-55

County Barber  
KANSAS



Elevation. 1533' DF

Production. 83 BO

CASING:

8 5/8" 125' cem w/100 sx  
5 1/2" 4308' cem w/150 sx

Figures indicate Bottom of Formations.

Meas. from top of Rotary Bushing.

red rock	125
red bed, shale & shells	525
shale & shells	1125
shale & shells & salt	1550
shale & lime	1705
lime & shale	1955
lime	1975
lime & shale	2125
lime	2230
lime & shale	2355
shale & lime	2535
shale & lime & sand	2740
shale & lime	2842
lime & shale	3225
shale & lime	3322
shale & sand	3390
lime & shale	3607
shale & sand	3641
lime	3818
lime & shale	3897
lime	4225
shale & lime	4246
chat	4260
lime (Miss.)	4308
Total Depth	

Tops: R.B.	
Elgin Sand	3375
Heebner	3506
Douglas Sand	3574
Brown Lime	3686
Lansing	3695
Harmaton	4151
Mississippi	4247

RECEIVED  
STATE CORPORATION COMMISSION

APR 22 1964

CONSERVATION DIVISION  
Wichita, Kansas