


R

WELL PLUGGING RECORD

15-087-30200-6000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Barber County, Sec. 25 Twp. 31 Rge. (E) 12 (W)
Location as "NE/CNW/SW" or footage from lines SE SW NE
Lease Owner Jayhawk Oil Co.
Lease Name Kissling Well No. 1
Office Address One Twenty Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed 9-9 1965
Application for plugging filed June 6 1968
Application for plugging approved June 7 1968
Plugging commenced June 10 1968
Plugging completed June 13 1968
Reason for abandonment of well or producing formation Non-commercial

If a producing well is abandoned, date of last production April 1968
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Elgin Sand Depth to top 3362 Bottom 3375 Total Depth of Well 3625 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface				8-5/8		None
				4-1/2		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

6/12 Sun Cementing Co. pumped 25 sacks gel & 15 sacks weight mud between 8-5/8" and 4 1/2" casing. Still flowing water in annulus.
6/13 Sun Cementing Co. pumped gel & weight mud between 8-5/8" and 5 1/2" casing. Shot casing @ 1600'. Pumped 75 sacks cement down 4 1/2" casing. Pumped 125 sacks cement down annulus between 8-5/8" & 4 1/2" casing. No pipe pulled. Plugging complete.

RECEIVED
STATE CORPORATION COMMISSION
JUL 1 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Braden-Deem, Inc.
Address 210 One Twenty Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss,
James B. Devlin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God,

(Signature) James B. Devlin
103 One Twenty Bldg. Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of July, 1969

My commission expires March 21, 1970

[Signature]
Notary Public.

WELL LOG #1 Kissling

15-007-30200-0000

Location: SE SW NE Sec 25-31-12W Barber Co. Kansas

Rotary Drilling Contractor: Sierra Petroleum Co., Inc

Commenced: June 15, 1965 Completed: September 2, 1965

Reertinate Data:

Elevation: 1525 K.B.	Sample Tops:	Elgin Sd	3358
		Heeb.	3486
Surf Pipe: 8 5/8 @ 210 feet w/175sk		U. Doug Sd	3547
		L. Doug Sd	3614
Prod Pipe: 4 1/2 @ 3455 w/100 sks		RTD	3625

Perforated Elgin w/52 shts from 3362-75. PB TD 3415

Test 500,000 CFGPD

RECEIVED
STATE CORPORATION COMMISSION
JUN 7 1968
CONSERVATION DIVISION
Wichita, Kansas