

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-21622-000

LEASE NAME Benifield

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 35 TWP. 31S RGE. 12 ~~W~~(W)

COUNTY Barber

Date Well Completed

Plugging Commenced 10-7-93

Plugging Completed 10-14-93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Graves Drilling Company

ADDRESS 8100 E. 22nd, P.O. Box 8250 Wichita, KS

PHONE#(316) 687-2777 OPERATORS LICENSE NO. 5428

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-7-93 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? yes

Producing Formation Depth to Top Bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 401 | None |
| | | | | 5 1/2 | 4470 | 3000 |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each section. Bridge plug at 3840, sanded up to 3700, spotted 5sx cement at 3700 with dump bailer, cut casing at 3000, pulled casing, pumped surface with 300 hulls, 10 gel, 50sx cement, 10 gel 100 hulls, 8 5/8 plug, 125sx cement, 60/40, 6%.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No.

Address P.O. Box 187, Medicine Lodge, KS 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Graves Drilling Company

STATE OF Kansas COUNTY OF Barber, ss.

Jeff Sletto (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Jeff Sletto

(Address) Medicine Lodge, KS 67104



SUBSCRIBED AND SWORN TO before me this 18 day of October, 1993

Glenda Morrison
Notary Public

My Commission Expires: Aug 17, 1994