

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 03/92

15-095-20519-0000

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-095-20,519-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR McCoy Petroleum Corporation KCC LICENSE # 5003 6-93  
(owner/company name) (operator's)

ADDRESS 110 South Main Suite 500 CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 265-9697

LEASE Early WELL# 1 SEC. 4 T. 30S R. 7W (East/West)

C - SE - SE - SPOT LOCATION/QQQQ COUNTY Kingman

735' FEET (in exact footage) FROM S/W (circle one) LINE OF SECTION (NOT Lease Line)

735' FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 236' CEMENTED WITH 175 SACKS

PRODUCTION CASING SIZE 4-1/2" SET AT 4223' CEMENTED WITH 300 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4084-4094'

ELEVATION 1452 1462 LTD T.D. 4509' PBD 4130' ANHYDRITE DEPTH \_\_\_\_\_  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Sand to 4034' and cap with 4 sacks of cement. Shoot pipe according to stretch. Pull pipe to 1200' and spot 30 sacks of cement. Pull pipe to 700' & spot 30 sacks of cement. Pull pipe to 290' & circulate cement to surface. Pull remaining casing & top off cement. 60/40 Pozmix 2% Gel. (Steve VanGieson KCC)  
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? \_\_\_\_\_ IS ACO-1 FILED? Yes

If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Daryl Hanson PHONE# (316) 532-5292

ADDRESS Kingman, KS City/State \_\_\_\_\_ 6-93

PLUGGING CONTRACTOR Clarke Corp. KCC LICENSE # 5105

ADDRESS 107 W Fowler, Medicine Lodge, KS 67104 PHONE # (316) 886-5665  
(company name) (contractor)  
STATE CORPORATION COMM. RECEIVED

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) \_\_\_\_\_ MAR 30 1993

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: \_\_\_\_\_ AUTHORIZED OPERATOR/AGENT: [Signature]  
(signature) CONSERVATION DIVISION  
Wichita, Kansas

27

Joan Finney  
Governor

Jim Robinson  
Chairman

F. S. Jack Alexander  
Commissioner

Rachel C. Lipman  
Commissioner

Judith McConnell  
Executive Director

Brian Moline  
General Counsel



# Kansas Corporation Commission

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

March 30, 1993

McCoy Petroleum Corp  
110 S Main 500  
Wichita KS 67202

Early 1  
API 15-095-20,519  
735'FSL-735'FEL  
Sec. 04-30-07W  
Kingman County

Dear Mr. Roger McCoy,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams  
Production Supervisor

Conservation Division  
William R. Bryson  
Director  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, Kansas 67202-1286  
Telephone (316) 263-3238

District: #2 202 W First Suite 304  
Wichita KS 67202  
(316) 263-8809