

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Sumner SEC. 3 TWP. 30S RGE. 4 E/W
Location as in quarters or footage from lines:
200' E of NE SW SW

Lease Owner Zenith Drilling Corporation
Lease Name Alexander Well No. 2
Office Address 505 Fourth Financial Ctr., Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): dry hole
Date Well Completed 6/18/82
Application for plugging filed 6/18/82
Plugging commenced 9:30 a.m. 6/18/82
Plugging completed 11:30 a.m. 6/18/82
Reason for abandonment of well or producing formation
no commercial quantities of oil or gas encountered
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Locate Well.
correctly on above
Section Platt.

Name of Conservation Agent who supervised plugging of this well Tim Galliher
Producing formation _____ Depth to top _____ bottom _____ T.D. 4431

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
<u>surface hole</u>	<u>shale</u>	<u>surf</u>	<u>256</u>	<u>8-5/8</u>	<u>254'</u>	<u>none</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fluid to 500', 50 sx
Fluid to 270', 30 sx
Fluid to 40', 15 sx, 1/2 sx hulls
Rat hole 5 sx

STATE RECEIVED
CORPORATION COMMISSION
JUN 23 1982
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor D N R DRILLING, INC.
515 R. H. Garvey Building
Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
James E. Donelson, Jr. (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) James E. Donelson, Jr.
515 R. H. Garvey Bldg., Wichita, Ks.
(Address) _____ 67202

SUBSCRIBED AND SWORN TO before me this 22nd day of June, 19 82

My Commission expires: April 30, 1983

Dorothy L. Schmidt
Notary Public.

DOROTHY L. SCHMIDT
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. April 30, 1983

DOROTHY L. SCHMIDT
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. April 30, 1983

DRILLER'S LOG

ZENITH DRILLING CORPORATION
Alexander #2
200' E of NE SW SW
Sec. 3-30S-4W
Sumner Co., Ks.

Commenced: 6-8-82
Completed: 6-18-82

Surface Casing: 254' of 8-5/8"
cmtd w/225 sx cmt, 3% cc, 2% gel

FORMATION

DEPTH

Surface Hole	0 - 256
Sand, Shale & Lime	256 - 505
Sand & Shale	505 - 921
Shale & Sand	921 - 1165
Shale & Lime	1165 - 1460
Lime & Shale	1460 - 1705
Shale & Lime	1705 - 1958
Lime & Shale	1958 - 2918
Shale & Lime	2918 - 3034
Lime & Shale	3034 - 3441
Lime	3441 - 3750
Lime & Shale	3750 - 4114
Lime	4114 - 4374
Shale & Lime	4374 - 4421
Sand	4421 - 4431 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson, Jr.
James L. Donelson, Jr.

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 22nd day of June, 1982.

Dorothy L. Schmidt
Dorothy L. Schmidt, Notary Public

DOROTHY L. SCHMIDT
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. April 30, 1983

STATE RECEIVED
CONSERVATION COMMISSION
JUN 23 1982
CONSERVATION DIVISION
Wichita, Kansas