

15-191-00331-2000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

SUMNER

County. Sec. 2 Twp. 30 Rge. (E) 2 (W)

Location as "NE/CNW/SW" or footage from lines SE SE SE
Lease Owner Shawver-Armour, Inc.
Lease Name Wightman Well No. 1
Office Address 817 Central Building
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7-20-56 19
Application for plugging filed 7-20-56 19
Application for plugging approved 7-20-56 19
Plugging commenced 7-20-56 19
Plugging completed 7-20-56 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Buffington
Producing formation None Depth to top 3714 Bottom 3742 Total Depth of Well 3742 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	water	0	409	8-5/8	409	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3742'-408' Fill w/heavy mud
408' Good permanent plug, then 1/2 sx hulls, 15 sx cement thru pipe then fill w/heavy mud
30' Good permanent plug, then 1/2 sx Hulls, then 10 sx cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shawver-Armour, Inc.
Address 817 Central Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
James Armour (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Armour
Shawver-Armour, Inc. James Armour
817 Central Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 26 day of July, 19 56

My commission expires December 29, 1959

Marjorie Hall
Marjorie Hall
Notary Public.
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC. 2 T. 30 R. 2W
BOOK PAGE 82 LINE 38

JUL 27 1956
7-27-56
CONSERVATION DIVISION
Wichita, Kansas

DRILLING LOG

COMPANY: Shawver-Armour, Inc.
 CONTRACTOR: Shawver-Armour, Inc.

LOCATION: SE SE SE
 Sec. 2-30S-2W
 Sumner County

FARM NAME: WIGHTMAN #1

ELEVATION: 1298 DF

COMMENCED: July 5, 1956

COMPLETED: July 20, 1956

CASING RECORD

8-5/8"

408'

w/350' ext. cam.

FORMATION	FROM	TO	
Surface Clay, Red Bed & Shale		40	
Shale, Salt & Gravel		300	
Salt around 250'			
Shale Shells & Salt		388	
Anhydrite		408	
Anhydrite, Shale & Lime Strks		540	
Lime & Shale		635	TOPS
Lime w/Shale Strks		678	Stalnaker 2752
Shale Lime Strks		705	Kansas City 3073
Shale & Shale w/Lime Strks		730	Mississippi 3714
Shale & Lime		770	R.T.D. 3742
Lime & Shale		820	
Lime & Shale, Sandy		865	
Lime & Shale		1075	
Shale & Lime Shells		1225	
Shale & Lime		1410	
Shale & Lime Strks		2020	
Shale & Lime		2180	
Lime & Shale		2285	
Shale & Lime		2460	
Lime & Shale		2789	
Shale & Sand		2875	
Shale & Lime		2960	
Shale w/Lime Strks		3078	
K. C. Lime & Shale		3130	
Lime & Chert		3174	
Lime		3275	
Lime & Shale		3291	
Shale & Lime		3360	
Lime & Shale		3659	
Shale & Lime		3718	
Mississippi Lime		3742	

STATE OF KANSAS) ss
 SEDGWICK COUNTY)

I, James Armour, do hereby certify that the above is a true and correct copy of the log on the above captioned well, as shown on the daily drilling reports.

SHAWVER-ARMOUR, INC.

By: James Armour
 James Armour, Sec. Treas.

Subscribed and sworn to before me this 26th day of July 1956.

My commission expires Dec. 29, 1959

Marjorie Hall
 Marjorie Hall, Notary Public

PLUGGING

FILE SEC 2 T 30 R 2W
 BOOK PAGE 82 LINE 38