

15-189-00167-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

N/A - Drilled
API NUMBER before 1967

LEASE NAME Carrie Winter

WELL NUMBER #1

SPOT LOCATION 2310 F.N.L.
1320 F.W.L.

SEC. 14 TWP. 31 RGE. 35 (E) OR (W)

COUNTY Stevens

DATE WELL COMPLETED 9/25/49

PLUGGING COMMENCED 2/27/84

PLUGGING COMPLETED 3/1/84

TYPE OR PRINT

PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR Mobil Oil Corporation

ADDRESS P. O. Box 5444, Denver, CO 80217

PHONE # (303) 298-2696 OPERATORS LICENSE NO. 5208

CHARACTER OF WELL Gas
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? District #1, 302 W. McArtor, Dodge City, KS

Is ACC-I FILED? FORWARDED IF NOT, IS WELL LOG ATTACHED? Will BE

PRODUCING FORMATION Hugoton DEPTH TO TOP 2588' BOTTOM 2756' T.D. 2819'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS | CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Towanda	gas	2732	2756	7"	2819'	0'
Hollenberg	gas	2588	2597	8 5/8"	650'	0'
Herrington	gas	2612	2628			
Krider	gas	2638	2668			
Winfield	gas	2681	2708			

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Set packer at 1432'. Pumped 4 sx of hulls and 33 sx of cement 2820' to 2603'. Pumped 7 sx of gel & 65 sx of cement 2565' to 2138'. Pumped 2 sx of gel. Pulled packer Welex set C.I.B.P. at 1390', put 5 sx of cement on top. Ran 2 3/8" tubing to 1350'. Circulated with 56 bbls. of gel. Pumped 52 sx cement 1250' to 1000'. Displaced tubing with 3.9 bbls. of gel. Pulled tubing to 700'. Pumped 42 sx cement 700' to 500' displaced tubing 1.9 bbls. of gel. Pulled tubing. Put bridge & 10 sx of cement 50' to 0. Cut off 10 3/4" & 7" 5 ft. below ground level & weld plate.

NAME OF PLUGGING CONTRACTOR Midwest Casing & Pulling LICENSE No. 6497
ADDRESS P. O. Box F, Sublette, Kansas 67877

STATE OF Kansas COUNTY OF Stevens, SS.

C. J. Park (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) C. J. Park
Mobil Oil Corporation
(ADDRESS) P. O. Box 5444, Denver, CO 80217

SUBSCRIBED AND SWORN TO BEFORE ME THIS 16 DAY OF April, 1984

Judith A. Olson
NOTARY PUBLIC

MY COMMISSION EXPIRES: 11-28-84

RECEIVED STATE CORPORATION COMMISSION FORM CP-4 REVISED 06-83

APR 18 1984

CONSERVATION DIVISION
Wichita, Kansas