

15-191-00561-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

SUMNER County. Sec. 31 Twp. 30 Rge. (E) 2(W)

Location as "NE/CNW/SW" or footage from lines NE SE NE

Lease Owner SHAWVER-ARMOUR, INC.

Lease Name CHITWOOD Well No. 1

Office Address 817 CENTRAL BLDG.

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed FEBRUARY 18, 1959

Application for plugging filed FEBRUARY 18, 1959

Application for plugging approved FEBRUARY 18, 1959

Plugging commenced FEBRUARY 18, 1959

Plugging completed FEBRUARY 18, 1959

Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well GENE GRAHAM

Producing formation Depth to top Bottom Total Depth of Well 4251 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE	WATER	0	150'	8-5/8"	213'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

HEAVY MUD TO 210'

#1 PLUG 210' HOWCO PLUG & 1/4 sk. HULLS . 15 SK. CEMENT .
IN DRY IF MUD LEVEL IS @ 210' IF NOT THRU DRILL PIPE.
THEN HEAVY MUD TO 30'.

#2 PLUG 30' HOWCO PLUG & 1/4 SK. HULLS 8 SK TO BASE OF CELLAR.

#3 2 SKS. IN RAT HOLE.

RECEIVED
CORPORATION COMMISSION

FEB 27 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor SHAWVER-ARMOUR, INC.

Address

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

JAMES M. ARMOUR (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James M. Armour
JAMES M. ARMOUR
817 Central Bldg. (Address)

SUBSCRIBED AND SWORN TO before me this 25th day of FEBRUARY, 1959

My commission expires December 29, 1959

MARJORIE HALL
MARJORIE HALL Notary Public.

PLUGGING
FILE SEC. 31 T. 30 R. 2W
BOOK PAGE 21 LINE 36

DRILLER'S LOG

FARM NAME: CHITWOOD # 1
CONTRACTOR: SHAWVER-ARMOUR, INC.
OWNER: SHAWVER-ARMOUR, INC.
COMMENCE: FEBRUARY 3, 1959

LOCATION: NE SE NE SEC. 31-30S-2W
SUMNER COUNTY, KANSAS
ELEVATION: 1344 K.B.
COMPLETED: FEBRUARY 18, 1959

CASING RECORD: 213' 8-5/8" W/165 SACKS CEMENT
2% CALCIUM CHLORIDE

=====

FORMATION:
Blue Shale 93
Keel & Hard Shale 360
Lime & Shale & Salt 525
Anhydrite 705
Lime & Shale 1180
Shale & Lime Streaks 1220
Lime & Shale 2899
Shale & Sand 2938
Shale & Lime 3024
Lime & Shale 3187
Kansas City Lime 3385
Lime & Shale 3803
Mississippian Lime 4048
Lime & Shale 4109
Mississippian 4146
Lime & Shale 4200
Simpson Sand 4250

TOPS:
Kansas City Lime 3155 (-1811)
Base Kansas City Lime 3391 (-2047)
Marmaton 3449 (-2105)
Mississippian 3801 (-2457)
Kinderhook 4162 (-2818)
Simpson Sand 4226 (-2882)

ROTARY TOTAL DEPTH 4251

RECEIVED
STATE CORPORATION COMMISSION
MAR 3 1959
CONF

STATE OF KANSAS)
)SS
SEDGWICK COUNTY)

I, James M. Armour, do hereby certify that the above log is a true and correct copy of the above captioned well as shown on the daily drilling reports.

SHAWVER-ARMOUR, INC.

BY James M. Armour
JAMES M. ARMOUR

Subscribed and sworn to before me this
28th day of February, 1959

My commission expires December 29, 1959

Marjorie Hall
MARJORIE HALL-NOTARY PUBLIC

PLUGGING
FILE SEC. 31 T30 R2W
BOOK PAGE 21 LINE 36