15-191-20312-0001


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Sumner County. Sec. 30 Twp. 30S Rge. (E) 2 (W)

Location as "NE/CNW¼SW¼" or footage from lines C NW SE

Lease Owner Hummon Oil, Inc.

Lease Name Pauly Well No. 1 OWWO

Office Address 821 Union National Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 2-10 19 72

Application for plugging filed 2-10 19 72

Application for plugging approved 2-10 19 72

Plugging commenced 2-10 19 72

Plugging completed 2-10 19 72

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gene Graham

Producing formation Depth to top Bottom Total Depth of Well 3178 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS — CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	This was a washdown of a previously plugged dry hole.					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole mudded to 240'
1/2 sack Hulls, plug, and 20 sacks cement
Mud to 40'
1/2 sack Hulls, plug, and 10 sacks cement
Rathole capped with 2 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
FEB 17 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor White & Ellis Drilling, Inc.

Address Box 448, El Dorado, Kansas 67042

STATE OF Kansas, COUNTY OF Butler, ss.

Ernest Sifford (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ernest Sifford

(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of February, 19 72

L. B. Auer

L. B. Auer Notary Public.

My commission expires September 26, 1972

L. B. AUER NOTARY PUBLIC BUTLER COUNTY, KANS.

15-191-20312-0001

CASING RECORD

8 5/8" 265' Cemented w/200 sacks

Total Depth 4215½'

KELLY BUSHING MEASUREMENT 5' ABOVE GROUND LEVEL

Location: C NW SE
Section: 30-30S-2W
Sumner County, Kansas
Farm: Pauly #1
Well Owner: Hummon Oil, Incorporated
Contractor: WHITE & ELLIS DRILLING, INC.
Commenced: 11-16-71
Completed: 11-29-71
Pauly #1 OWWO
Commenced: 2-8-72
Completed: 2-10-72
Did Not Deepen Well

FORMATION	DEPTH	
Cellar & Sod	0-15	
Shale & Lime	515	
Lime w/Shale (Stks.)	655	
Shale & Lime	1444	
Shale	1790	
Lime & Shale	1810	
Shale & Lime (Sdy)	2040	
Lime & Shale	2315	
Shale & Lime (Stks.)	2460	
Lime & Shale	2765	
Shale	2926	
Sand	2950	
Shale	3148	
Lime	3390	
Shale & Lime	3465	DRY HOLE
Shale & Lime (Stks.)	3675	
Shale	3780	PLUGGED & ABANDONED
Lime	3783	
Core #1	3789	
Lime	4133	
Shale	4204	
Sand	4210	
Core #2	4215½	

TOPS

Kansas City	3148
Mississippi	3780
Simpson	4204

RECEIVED
STATE CORPORATION COMMISSION
FEB 17 1972
CONSERVATION DIVISION
Wichita, Kansas