

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Sumner SEC. 30 TWP. 30s RGE. 2 w E/W
Location as in quarters or footage from lines:

C/S/2 SW SW

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |

Lease Owner Sanders Oil Co.

Lease Name McNett Well No. 1

Office Address 910 Sutton Place Wichita, Ks. 67202

Character of Well (Completed as Oil, Gas or Dry Hole): oil

Date Well Completed _____

Application for plugging filed _____

Plugging commenced 4-12-81

Plugging completed 4-14-81

Reason for abandonment of well or producing formation _____

Depleted

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Barnett

Producing formation _____ Depth to top _____ bottom _____ T.D. 3798'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

| Formation | Content | From | To | Size | Put in | Pulled Out |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 215' | none |
| | | | | 5 1/2 | 3784 | 1254' |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded hole to 3770 set five sks. cement with bailer

Recovered 1254' of 5 1/2" casing

Set rock bridge at 250' and filled hole with four yds. of ready mixed cement

RECEIVED
STATE CORPORATION COMMISSION

JUN - 9 1981

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Voth Casing Pulling

CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas COUNTY OF Cowley, ss.

Walter Voth (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) Walter Voth
715 South A Arkansas City Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 15 day of April, 1981

Milton Harris
Notary Public.

My Commission expires: _____

DUNBAR DRILLING INC.
 5252 NORTH BROADWAY
 WICHITA, KANSAS 67219
 (316) 832-0501

COMPANY CHAS. W. SANDERS OIL CO., INC.
 FARM McNett
 WELL No. 1
 LOCATION C S/2 SW SW/4 Section 30-30S-2W
 Sumner County, Kansas
 CASING RECORD 8 5/8" @ 215'/200 sax.
 4 1/2" @ 3798'
 COMMENCED 9-7-77
 COMPLETED 9-20-77
 DRILLING CONTRACTOR

DUNBAR DRILLING INC.
 5252 NORTH BROADWAY
 WICHITA, KANSAS 67219

DRILLERS LOG

| | |
|------|--------------------------------|
| 0-7 | soil |
| 217 | shale |
| 779 | shale & lime |
| 1345 | lime & shale with sand streaks |
| 1998 | shale & lime |
| 2365 | shale |
| 2845 | shale & sand |
| 3325 | sand |
| 3605 | lime |
| 3750 | shale |
| 3798 | lime & shale & sand |
| 3798 | R. T. D. |