

15-191-30192-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


67

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Sumner County. Sec. 28 Twp. 30 Rge. 2 (E) E (W)

Location as "NE/CNW/SW" or footage from lines C SE SE  
Lease Owner O. A. Sutton  
Lease Name Wise Well No. 1  
Office Address 800 Sutton Place, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 1-3/1967  
Application for plugging filed 1-3/1967  
Application for plugging approved 1-3/1967  
Plugging commenced 1-3/1967  
Plugging completed 1-3/1967  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Paul Turpin  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3882 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	513'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded hole with 40 vis. mud to 225 ft.  
Added 1/2 sack of hulls. Set a dry hole plug  
add3d 20 sacks of cement. Mudded hole from  
this point to 35 ft. Added hulls, plug and  
8 sacks of cement. Capped rathole with 2  
sacks of cement.

15-191-30192-0000  
STATE CORPORATION COMMISSION  
JAN 9 1967  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor WHITE & ELLIS DRILLING, INC. License #209  
Address Box 448, El Dorado, Kansas 67042

STATE OF Kansas, COUNTY OF Butler, ss.  
Ernest Sifford, employee of contractor \_\_\_\_\_ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ernest Sifford  
Box 448, El Dorado, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of K M January, 19 67

My commission expires September 26, 1968

Notary Public.

15-191-30192-0000 6P

**BUSHING RECORD**

8 5/8

513' Cemented  
w/325 sacks

Location: C SE SE  
Section: 28-30S-2W  
Sumner County, Kansas  
Farm: Wise #1  
Well Owner: O.A. Sutton  
Contractor: WHITE & ELLIS  
DRILLING, INC.  
Commenced: 12-18-66  
Completed: 1-2-67

T. D.

3882'

KELLY BUSHING MEASUREMENT 5' ABOVE GROUND LEVEL.

<u>FORMATION</u>	<u>DEPTH</u>
Shale & Lime	0-128
Shale & Lime	430
Shale	498
Anhydrite	514
Lime & Shale	1230
Lime - broken	1360
Shale & Lime	1984
Lime	2012
Lime & Shale	2104
Lime	2128
Shale & Lime	2370
Shale	2678
Shale & Lime	2844
Shale	2870
Sand	2926
Shale & Lime	3146
Lime	3393
Shale	3422
Shale & Lime	3641
Shale & Shells	3740
Shale	3825
Lime	3882

TOPS

Anhydrite	498
Topeka	2104
Stalnaker	2870
Kansas City	3146
Mississippi	3861

Dry Hole, Plugged  
& Abandoned

Core #1 3794 - 3825

RECEIVED  
OIL & GAS CORPORATION COMMISSION  
JAN 9 1967  
CONSERVATION DIVISION  
Wichita, Kansas