


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Sumner County. Sec. 27 Twp. 30S Rge. 2 (W)
Location as "NE/CNW/SW" or footage from lines SE SE NE
Lease Owner Pickrell Drilling Company
Lease Name Kibbe Well No. 1
Office Address 705 Fourth Nat'l. Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 27 1957
Application for plugging filed December 27 1957
Application for plugging approved December 27 1957
Plugging commenced December 27 1957
Plugging completed December 27 1957
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eugene Graham
Producing formation Depth to top Bottom Total Depth of Well 3885 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	200'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 190', bridge hole and cement with 15 sacks cement. Then heavy mud to 20' below ground level, bridge hole and cement with 10 sacks cement to bottom of cellar.

STATE CORPORATION COMMISSION

CONSERVATION DIVISION
Wichita

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. W. Sebitts (employed by owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705-4th Nat'l. Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of January, 1958

My commission expires July 30, 1958
Notary Public.

PLUGGING
FILE SEC 27 T 30 R 2W
BOOK PAGE 73 LINE 13

15-191-00691-0000 ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company

Rotary Drilling Commenced 12/14/57

LOCATION: SE SE NE Sec. 27-30-2W

Rotary Drilling Completed 12/27/57

Kibbe No. 1

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

CASING RECORD: 5 jts. 200' 8 5/8" Armco Spiralweld cemented, with 135 sacks cement circulated.

No oil string, D & A

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

Shale	110	Circ. for samples at	3160
Shale & Lime	200		3840
Shale & Shells	400		3860
Lime	1130		
Lime & Shale	1695		
Shale & Lime, Shells	1840		
Lime & Shale	2515		
Shale & Lime	2738		
Lime & Shale	2886		
Shale & Lime	2980		
Shale	3060		
Lime & Shale	3140		
Lime	3250		
Lime & Shale	3327		
Lime	3367		
Lime & Shale	3506		
Shale & Lime	3607		
Lime & Shale	3692		
Shale & Lime	3794		
Mississippi	3885 T.D.		

S.L.M. at 1500 - O.K.
2500 - "
3500 - "

Slope Test at 1500 0° off
2500 0° off
3500 0° off

RECEIVED
STATE CORPORATION COMMISSION

JAN 7 1958

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING

FILE SEC 27 T 30 R 20
BOOK PAGE 73 LINE 13

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By

Attorney-in-Fact

STATE OF KANSAS
COUNTY OF SEDGWICK

On this 6 day of January, 19 58, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: July 30, 1958

Notary Public