

STATE OF KANSAS
STATE CORPORATION COMMISSION
209 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-191-21,067-0000

LEASE NAME STEPHEN J. LANGE-
ANSON

WELL NUMBER 1

SPOT LOCATION NE SW SW

SEC. 25 TWP. 30 RGE. 2w (E) OR (W)

COUNTY SUMNER

DATE WELL COMPLETED 8-29-80

PLUGGING COMMENCED 9-26-83

PLUGGING COMPLETED 10-6-83

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR MIDWESTERN SUPPLY CO. INC.

ADDRESS 300 PATTON RD. GREATBEND, KS. 67530

PHONE #(316) 793-8521 OPERATORS LICENSE NO. 8778

CHARACTER OF WELL OIL
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? YES

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? DIST. #2

IS ACC-1 FILED? IF NOT, IS WELL LOG ATTACHED? YES

PRODUCING FORMATION DEPTH TO TOP BOTTOM T.D. 3818'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"		2,834.25'

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. SANDED BACK TO 3175' WITH 4 SACKS OF CEMENT.

UNITED CEMENTING CAME OUT AND PUMPED DOWN 3 HULL; 6 GEL; 170 SACKS OF COMMON CEMENT WITH 3% C.C. . MAX. PRESSURE 500 LBS. SHUT IN AT 200 LBS. AT 11:30 A.M. .

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR H&H CASING PULLING CO.

LICENSE No. 6052


ADDRESS 1427 N. HALSTEAD HUTCHINSON, KS 67501

STATE OF KANSAS COUNTY OF RENO, SS.

DONALD H. HURST (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) Donald H. Hurst
FINEST MOBILE HOME PARK LOT 78
(ADDRESS) GREAT BEND, KS. 67530

SUBSCRIBED AND SWORN TO BEFORE ME THIS 10th DAY OF October, 1983



MY COMMISSION EXPIRES: _____

Madeline Hurst
NOTARY PUBLIC

RECEIVED
STATE CORPORATION COMMISSION

OCT 12 1983
FORM CP-4
REVISED 06-83

CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

Well Name: #1 Stephen J. Lange-Anson Operator: Wheatland Oil & Gas, Inc.
 Spud Date: 8-21-80 Contractor: Ramco Drilling Corp.
 Completion Date: 8-29-80 Casing: 8 5/8" @ 456' w/ 250 sx.
 Location: NE SW SW Sec. 25-30S-2W 4 1/2" @ 3817' w/ 200 sx.
 Sumner County, Kansas

FORMATION

API 15-191-21068

FORMATION	FROM	TO
Surface & Shale	0	100
Sand & Shale	100	456
Shale	456	1215
Shale & Sand	1215	1555
Shale & Lime	1555	1820
Shale	1820	3299
Shale & Lime	3299	3547
Lime & Shale	3547	3818
Rotary Total Depth	3818	

11:30

May 500

Start in 200

3818
 800

 3018

CT P100 3310
 Perf 3270 - 3278'
 3227 3230'

from 3 sec
 one mile North 1/2 East on North side of
 Rd.

Sand Back 3227
 30
 3175 (W) 4 feet.

STATE OF KANSAS, COUNTY OF BUTLER: ss

I certify that the above information is true and correct to the best of my knowledge.

RECEIVED
 STATE CORPORATION COMMISSION

OCT 12 1983

THE RAMCO DRILLING CORPORATION


J. V. Crawford
 J. V. Crawford, Vice President

Subscribed and sworn to on this 25th day of September, 1980

CONSERVATION DIVISION
 Wichita, Kansas

Sandra Kay May
 Sandra Kay May Notary Public

My appt. exp:



COPY FOR YOUR INFORMATION