

15-191-00328-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Summer County. Sec. 24 Twp. 30 Rge. (E) 2 (W)
Location as "NE/CNW/SW" or footage from lines. NW NW SE
Lease Owner Renfro Drilling Co.
Lease Name Castholm Well No. 1
Office Address 316 Insurance Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-26 19 56
Application for plugging filed 10-26 19 56
Application for plugging approved 10-26 19 56
Plugging commenced 10-26 19 56
Plugging completed 10-26 19 56
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. G. Buffington
Producing formation Depth to top Bottom Total Depth of Well 4136 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug #1 at 460 feet from surface. Mixed 15 sacks cement, filled with mud to 30 feet from surface. Set plug #2 at 30 feet, filled with 10 sacks cement. Welded steel plate on top of pipe at 30 inches from ground level.

RECEIVED
STATE CORPORATION COMMISSION
NOV-2-1956
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Renfro Drilling Co.
Address 316 Insurance Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Henry D. Ficken (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Henry D. Ficken
316 Insurance Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 31st day of October, 1956

My commission expires May 4, 1959
Joanne Leslie Notary Public.

24-7368-5 3-53-20M

PLUGGING
FILE SEC 24 T. 30 R. 2W
BOOK PAGE 111 LINE 35

Operator - RENFRO DRILLING CO.
 Well - CASTHOLM #1
 Location - NW NW SE Sec. 24-30S-2W
 Summer County, Kansas
 Commenced - 10-12-56
 Completed - 10-26-56
 Casing - 8 5/8" at 462' w/200 sx cement
 Elevation - 1306 Rotary Bushing

DRILLERS' LOG

0 - 50	Sand	3111 - 3131	Lime
50 - 277	Shale and shells	3131 - 3170	Lime
277 - 287	Lime and Anhydrite	3170 - 3175	Lime
287 - 395	Shale, Anhydrite & salt	3175 - 3262	Lime
395 - 406	Anhydrite	3262 - 3304	Lime
406 - 460	Shale and Anhydrite	3304 - 3310	Shale
460 - 462	Anhydrite	3310 - 3415	Shale and lime
462 - 475	Anhydrite	3415 - 3490	Shale and lime
475 - 495	Shale and anhydrite	3490 - 3570	Lime and shale
495 - 790	Shale and shells	3570 - 3675	Lime and shale
790 - 975	Lime and shale	3675 - 3720	Shale and lime
975 - 1205	Lime and shale	3720 - 3728	Shale
1205 - 1465	Shale and shells	3728 - 3735	Lime
1465 - 1735	Lime and shale	3735 - 3779	Lime and dolomite
1735 - 1900	Shale	3779 - 3823	Lime
1900 - 1985	Lime and shale	3823 - 3877	Lime
1985 - 2170	Lime	3877 - 3912	Lime
2170 - 2370	Lime and shale	3912 - 3943	Lime
2370 - 2530	Lime and shale	3943 - 3975	Lime
2530 - 2640	Lime and shale	3975 - 4012	Lime
2640 - 2802	Lime and shale	4012 - 4053	Lime and chert
2802 - 2837	Sand and shale	4053 - 4104	Lime
2837 - 2975	Sand and shale	4104 - 4129	Lime and shale
2975 - 3067	Sand and shale	4129 - 4135	Sand
3067 - 3111	Lime	4135 -	Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 NOV - 6 1956
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
)ss
 COUNTY OF SEDGWICK)

PLUGGING
 FILE SEC 24 T 30 R 2W
 BOOK PAGE 111 LINE 35

I, the undersigned, being duly sworn on oath, state that the above Drillers' Log is true and correct to the best of my knowledge and belief and according to the records of this office.

RENFRO DRILLING CO.

By Henry S. Fickler

Subscribed and sworn to before me this 31st day of October, 1956.

My commission expires May 4, 1959.

Joanna Leake
 Notary Public