

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-191-01147-0000  
 Well was completed on:

API NUMBER 2-6-60

LEASE NAME Daley

WELL NUMBER 3

1650 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 5 TWP. 30SRGE. 2 (E) ~~xxxx~~

COUNTY Sumner

Date Well Completed 2-6-60

Plugging Commenced 3-7-91

Plugging Completed 3-11-91

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 26100, Oklahoma City, OK 73126-0100

PHONE#(405) 749-2471 OPERATORS LICENSE NO. 5447

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on February 28, 1991 (date)

by Mr. Steve Van Gieson of District Office #4 (KCC District Agent's Name).

Well was completed on:  
 Is ACO-1 filed? 2-6-60 if not, is well log attached? Yes

Producing Formation LKC Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
LKC	Oil	3132	3171	8 5/8"	231'	-
				5 1/2"	3206'	2317'

MAR 29 1991

CONSERVATION DIVISION  
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pulled 103 its of 2 3/8" tubing (3180'). Filled csg w/sand to 3080'. Dumped 5 sx cmt. Pulled 70jts 5 1/2" csg (2317'). Ran 23 its tubing spotted 2 sx hulls. Pulled 3 its to 610'. Pumped 35 sx 65/35 Poz. Displaced. Ran wire line and tagged at 430'. Mixed 2 sx Hulls. Displaced. Pulled tubing to 300'. Mixed 315 sx 65/35 Poz and circulated to surface. P & A completed. State Witness: Mr. Steve Van Gieson. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clark Well Services License No. \_\_\_\_\_

Address Wichita, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Bryan Humphries (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bryan Humphries

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 25th day of March, 19 91

Kay Ann Blome  
 Notary Public

My Commission Expires: 4-16-94