

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-129-00075-0000 (of this well) 6/87  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Amoco Production Company OPERATORS LICENSE NO. 5952  
ADDRESS P. O. Box 432 Liberal, Kansas 67901 PHONE # (316) 624-6241  
3300 FSL x  
LEASE (FARM) Bonham G.U. B WELL NO. 1 WELL LOCATION 1980 FEL COUNTY Morton  
1980 FEL  
SEC. 24 TWP. 32S RGE. 40  (O)  (W) TOTAL DEPTH 6000 PLUG BACK TD 5840

Check One:

OIL WELL \_\_\_\_\_ GAS WELL  D & A \_\_\_\_\_ SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_  
SURFACE CASING SIZE 8-5/8" SET AT 705' CEMENTED WITH 500 SACKS  
CASING SIZE 4-1/2" SET AT 5964 CEMENTED WITH 200 SACKS  
PERFORATED AT 5815-5817, 5853-55, 5798-5822

CONDITION OF WELL: GOOD  POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL \_\_\_\_\_

See Attached

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? Yes  
Per recent telcon with commission (If not, explain)  
not necessary for this well.  
DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 7-29-86 8:00 a.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Paul Jones PHONE # (316) 356-1237  
ADDRESS P. O. Box 507 Ulysses, KS 67880

PLUGGING CONTRACTOR To be bid LICENSE NO. \_\_\_\_\_

ADDRESS \_\_\_\_\_ PHONE # ( ) \_\_\_\_\_

PAYMENT WILL BE GUARANTEED BY OPERATOR 1986 AGENT SIGNED: [Signature]  
(Operator or Agent)

STATE CORPORATION COMMISSION

CONSERVATION DIVISION  
Wichita, Kansas

DATE: 7-14-86

①



Amoco Production Company

P. O. Box 432  
Liberal, KS 67901

July 11, 1986

File: RAR-524-400.1

Recommended Plugging and Abandonment Procedure  
Bonham G. U. "B" No. 1  
Section 24-32S-40W  
Morton County, Kansas

Detailed below is the recommended plugging and abandonment procedure for the subject well. Note that this procedure is for permitting purposes only.

1. MIRUSU or casing pullers, and pull 2 3/8" tubing.
2. Run a gauge ring and CIBP, set CIBP at 5700', cap with 2 sacks cement.
3. Locate free point of 4 1/2" casing (see attached wellbore sketch), cut off and pull casing. Estimated top of cement is 5100'.
4. Spot a 50 sack 50-50 Poz cement plug across the 4 1/2" casing stub.
5. Spot a 75 sack cement plug across the 8 5/8" surface casing shoe (50' in and out of casing shoe), shoe set at 705'.
6. Spot a 50 sack cement plug from 40-5'.
7. Dig out cellar, cut off surface casing at 5'. Weld on steel cap with well and location I.D.
8. Restore location.

NOTE: All intervals between cement plugs must contain mud of at least 9.0 ppg density, and 36 quart-second API viscosity. A representative of the KCC must be notified at least five days prior to the actual plugging operation to discuss plugging methods. They (KCC) can be contacted at (316) 225-6760.

C. H. Kelm

BSP/sac

RECEIVED  
STATE CORPORATION COMMISSION

JUL 15 1986

CONSERVATION DIVISION  
Wichita, Kansas

State of Kansas



JOHN CARLIN  
MICHAEL LENNEN  
MARGALEE WRIGHT  
KEITH R. HENLEY  
JUDITH A. McCONNELL  
BRIAN J. MOLINE

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary  
General Counsel

## State Corporation Commission

### CONSERVATION DIVISION

(Oil, Gas and Water)  
200 Colorado Derby Building  
202 West 1st Street  
WICHITA, KANSAS 67202-1286

THIS NOTICE  
OCT 21 1986

July 21, 1986

EXPIRES

### WELL PLUGGING NOTICE

*Correction* →

Bonham G. U. "B" #1  
3300' FSL 1980' FEL  
Sec. 24-32S-40W  
Morton County

Amoco Production Company  
P. O. Box 432  
Liberal, KS 67901

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

Jack McCord, Director

Please contact the district office to review your suggested method of plugging  
DIST. #1 302 West McArtor Dodge City, KS 67801 316-225-6760  
five days prior to plugging the well (KAR-82-3-113).